

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JUN 23 1965

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name H. C. Bennett
 Complete Address: 1212 Union National Bldg., Wichita, Kansas
 Lease Name Greenstreet Well No. # 1
 Location SW NW SE Sec. 31 Twp. 27 Rge. 13 (E) (W) W
 County Pratt Total Depth 4526'
 Abandoned Oil Well X Gas Well Input Well SWD Well D & A
 Other well as hereafter indicated:
 Plugging Contractor: Flint Engineering & Construction Company
 Address: Box 950 EL Dorado, Kansas License No. 547
 Operation Completed: Hour 5:00 PM Day 21st Month June Year 1965

The Above well was plugged as follows:

360' of 8 5/8" surface pipe, cement circulated. 4524' of 5 1/2" long string,
cemented with 100 sacks. Plug back to 4493'. Top perferation 4416'. Bottom
of the hole was sanded to 4400', and cemented with 5 sacks. 3960' of 5 1/2"
long string was recovered from the hole. Fluid was up in the hole. Bridge
plug was pushed in fluid to 270', and 10' of rock bridge on plug. 2 sacks
of cement and 10% Calcium Chloride was mixed in barrel and put on plug at
260', through the dump bailer. And let set for 1 1/2 hours. Hole was bailed
dry and 23 sacks of cement was added to the plug. Hole was filled with mud
to 40', and 10' of rock bridge, and cemented with 10 sacks to the base of
the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 6/23/65

INV. NO. 1358-W

Signed: Archie Elving
Well Plugging Supervisor