

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JUL 19 1965

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name H. C. Bennett

Complete Address: 1212 Union National Bldg., Wichita, Kansas

Lease Name Elliott "A" Well No. # 4

Location SE SW SE Sec. 31 Twp. 27 Rge. 13 (E) (W) W

County Pratt Total Depth 4460'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Flint Engineering & Construction Company

Address: Box 950, El Dorado, Kansas License No. 547

Operation Completed: Hour 9:45 AM Day 16th Month July Year 1965

The Above well was plugged as follows:

368' of 8 5/8" surface pipe, cement circulated. 4459' of 5 1/2" long string,
cemented with 150 sacks. Plug back to 4425'. Top perferation 4385', Bottom
of the hole was sanded to 4375', and cemented with 5 sacks. 2400' of 5 1/2"
long string was recovered from the hole. Fluid was up in the hole. Bridge
plug was pushed in fluid to 290', and 10' of rock bridged on plug. 5 sacks
of cement was mixed in barrel, and put on plug at 280', through the dump
bailer, and let set over-night. Next morning hole was bailed dry, and 20
sacks of cement was added to the plug. Hole was filled with mud to 40', and
10' of rock bridged, and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 7/20/65

INV. NO. 1479-u