

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 15 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name H. C. Bennett

Complete Address: 1212 Union National Bank Bldg., Wichita, Kansas

Lease Name Elliott "A" Well No. # 2

Location S/2 SE SW Sec. 31 Twp. 27 Rge. 13 (E) (W) W

County Pratt Total Depth 4530'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Flint Engineering & Construction Company

Address: Box 950, El Dorado, Kansas License No. 547

Operation Completed: Hour 4:00 PM Day 13th Month July Year 1965

The Above well was plugged as follows:

360' of 8 5/8" surface pipe, cement circulated. 4528' of 5 1/2" long string,
cemented with 150 sacks. Plug back to 4449'. Top perferation 4416'. Bottom
of the hole was sanded to 4400', and cemented with 5 sacks. 2400' of 5 1/2"
long string was recovered from the hole. Fluid level was up in the hole.
Bridge plug was pushed in fluid to 290', and 10' of rock bridge on plug.
4 sacks of cement and 10% Calcium Chloride was mixed in barrel, and put
on plug at 280', through the dump bailer, and let set for 1 1/2 hours. Hole
was bailed dry, and 21 sacks of cement was added to the plug. Hole was filled
with mud to 40', and 10' of rock bridge, and cemented with 10 sacks to the
base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 7/15/65

INV. NO. 1461-W