

Form CP-3  
Rev. 6-26-62KANSAS  
STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION76-65  
JUL 6 1965CONSERVATION DIVISION  
Wichita, KansasJ. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, KansasOperator's Full Name H. C. BennettComplete Address: 1212 Union National Bldg., Wichita, KansasLease Name Elliott "A" Well No. # 1Location SW SE Sec. 31 Twp. 27 Rge. 13 (E) (W) WCounty Pratt Total Depth 4543'Abandoned Oil Well X Gas Well  Input Well  SWD Well  D & A Other well as hereafter indicated: Plugging Contractor: Flint Engineering & Construction CompanyAddress: Box 950, El Dorado, Kansas License No. 547Operation Completed: Hour 10:45AM Day 2nd Month July Year 1965

The Above well was plugged as follows:

362' of 8 5/8" surface pipe, cement circulated. 4527' of 5 1/2" long string, cemented with 100 sacks. Plug back to 4480'. Top perferation 4412'. Bottom of the hole was sanded to 4400', and cemented with 5 sacks. Pipe was pulled off, and 1500' of 5 1/2" long string was recovered from the hole. Fluid level was up in the hole. Bridge plug was pushed in fluid to 290', and 10' of rock bridge on plug. 2 sacks of cement and 10% Calcium Chloridge was mixed in barrel, and put on plug at 280', through the dump bailer. And let set for 1 1/2 hours. Hole was now bailed dry, and 23 sacks of cement was added to the plug. Hole was filled with mud to 40', and 10' of rock bridge, and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging SupervisorDATE 7-6-65INV. NO. 1410-W