

K  
KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

**RECEIVED**  
STATE CORPORATION COMMISSION  
7-16-65  
JUL 16 1965

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name H. C. Bennett

Complete Address: 1212 Union National Bldg., Wichita, Kansas

Lease Name Elliott "A" Well No. # 3

Location C S/2 S/2 S/2 Sec. 31 Twp. 27 Rge. 13 (E) (W) W

County Pratt Total Depth 4475'

Abandoned Oil Well . X Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated:

Plugging Contractor: Flint Engineering & Construction Company

Address: Box 950, El Dorado, Kansas License No. 547

Operation Completed: Hour 9:45 AM Day 15th Month July Year 1965

The Above well was plugged as follows:

359' of 8 5/8" surface pipe, cement circulated. 4472' of 5 1/2" long string,  
cemented with 150 sacks. Plug back to 4442'. Top perforation 4399'. Bottom  
of the hole was sanded to 4390', and cemented with 5 sacks. 2400' of 5 1/2"  
long string was recovered from the hole. Fluid was up in the hole. Bridge  
plug was pushed in fluid to 290', and 10' of rock bridge on plug. 5 sacks  
of cement was mixed in barrel and put on plug at 280', through the dump  
bailer, and let set over-night. Next morning hole was bailed dry, and 20  
sacks of cement was added to the plug. Hole was filled with mud to 40', and  
10' of rock bridge, and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

DATE 7/16/65

INV. NO. 1466-W

Signed: Annie Elving  
Well Plugging Supervisor