

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Pratt

Location: SE NW SE Sec. 10 Twp. 27 Rge. 15 (E) (W)

Name of Field: _____ Total Depth: 4717

I have this date completed supervision of plugging of:

Lease Name: Cochran Well No. 2

Operator's Full Name: Osage Oil & Gas Co.

Complete Address: 531 Petroleum Bldg., Wichita, Kans.

Plugging Contractor: E & L. Casing Pulling Co.

Address: Great Bend, Kans. License No. 377

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 1 PM Day 7 Month May Year 1958

The above well was plugged as follows:

301' of 8 5/8" surface casing circulated with cement. Top perf: 4408 1/2-
4411 1/2'. Sand to 4407' with five sack cement dumped with dump bailer.
Mud was circulated at about 1700'. Hole was filled to 310' with heavy
jell mud with rock bridge set at 310' and 20 sack cement on top bridge.
Heavy mud to 35' with rock bridge set and 10 sack cement to fill hole.

Signed:
Conservation Division Agent

Reviewed:
Field Supervisor

Remarks:

PLUGGING
FILE SEC. 10 T. 27 R. 15 W
BOOK PAGE 100 LINE 29

RECEIVED
STATE CORPORATION COMMISSION
574-58
MAY 14 1958