

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

15-151-20310-0001
API Number 15 - - (of this well)

Operator's Full Name Texas Energies, Inc.

Complete Address 306 Bank of the Southwest Bldg., Amarillo, Texas, 79109

Lease Name McBride Well No. 1

Location C SW SE Sec. 27 Twp. 27S Rge. 14 (E) (W) X

County Pratt Total Depth 4640

Abandoned Oil Well Gas Well Input Well ✓ SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Sargent's Casing Pulling.

Address 620 S. Lincoln Liberal, Ks. 67901 License No. 511

Operation Completed: Hour 2:30 Pm. Day 23 Month 5 Year 1979

The above well was plugged as follows:

329' 8 5/8" casing w/350 sax cement. 4 1/2" casing set at 4215' w/150
sax cement. Preforated at 3914'-3930'-Sargent mixed & pumped 35 sax
cement-Release plug, mixed & pumped 20 sax gel in 5 1/2" casing pumped
plug to 3075'-Shut in w/1900# pressure. Pull 2607' 5 1/2" casing. Spot
40 sax cement at 294'-Build bridge at 40' & 12 sax cement to top of
casing.

STATE CORPORATION COMMISSION

MAY 25 1979

CONSERVATION DIVISION
Liability Bureau

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 5-30-79

INV. NO. 9723-W

Signed: [Signature]
Well Plugging Supervisor