

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 2 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Gene Risley

Complete Address 6015 Clarendon Wichita, Ks 67220

Lease Name Cromer Well No. 1

Location NW/SE Sec. 8 Twp. 27 Rge. 14 (E) (W) X

County Pratt Total Depth 4617

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Knight Casing Pulling Co.

Address Box 405 Chase, Ks License No. 436

Operation Completed: Hour 10:30 AM Day 27 Month 2 Year 1970

The above well was plugged as follows:

330 ft of 8 5/8 surface pipe circulated with 330 sacks cement. 4180

ft of 4 1/2 long string cemented with 100 sacks cement. P.B. at 4145

ft. Perf at 4076. Sand Back to 4000 ft., 5 sacks cement with bailer.

Pulled 3604 ft of 4 1/2. Fill hole to 250 ft, 10 ft rock bridge & 25

sacks cement. Mud to 40 ft, 10 ft. rock bridge & 10 sacks cement

to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 3/2/70
INV. NO. 1518-W