

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Kiowa County.

Sec. 17 Twp. 29S Rge. 2E (E) 17 (W)

Location as "NE/CNW/SW" or footage from lines C E/2 W/2 SE/4

Lease Owner Sunray Mid-Continent Oil Company

Lease Name A. Campbell Well No. 1

Office Address Box # 788, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed June 22 1957

Application for plugging filed June 24 1957

Application for plugging approved June 24 1957

Plugging commenced June 22 1957

Plugging completed June 22 1957

Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundege

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4788 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	409'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Hole filled w/ drlg mud, 1/4 sack hulls, Halliburton plug at 370', 35 sacks cement on plug. Hole filled w/ drlg. mud, 3/4 sack hulls & Halliburton plug @ 45', ran 15 sacks cement on plug, cement to surface. Plugging completed.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 28 1957 6-28-57  
CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor Halliburton Oil Well Cementing Co.  
Address \_\_\_\_\_

STATE OF KANSAS COUNTY OF BARTON ss.

N. E. Montgomery (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) N. E. Montgomery  
Box # 788, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 25 day of June, 1957

My commission expires 10-17-59

Inogene Post  
Notary Public.

PLUGGING  
FILE SEC 17 T. 29 R. 17 W  
BOOK PAGE 23 LINE 3

Sunray Mid-Continent Oil Company  
Tulsa, Oklahoma

Tulsa, Oklahoma  
June 25, 1957

CONTRACTOR: Stickle Drilling Company  
Drilling Commenced: June 4, 1957  
Drilling Completed: June 22, 1957

A. Campbell #1 - SE/4 of  
Section 17-27S-17W, Kiowa  
County, Kansas.

DRILLERS LOG

Depth Figures Indicate Base of Formation

Sand & Shale	225
Shale & Shells	360
Red Bed	412
Sand & Shale	450
Anhydrite	485
Shale & Shells	1317
Shale	1740
Lime & Shale	2180
Lime	2300
Lime & Shale	2515
Lime	2650
Lime & Shale	2735
Lime	2905
Shale	2950
Shale & Lime	3110
Lime & Shale	3575
Shale	3685
Shale & Lime	3750
Lime	3855
Lime & Shale	3995
Lime	4103
Lime & Shale	4161
Lime	4462
Shale & Lime	4507
Lime	4725
Chat	4727
Cherty Lime	4761
Cherty Lime & Sand	4788 TD

I, Frank E. Stickle, hereby certify the above to be a true and complete Driller's Log of Sunray Mid-Continent Oil Company's A. Campbell #1 - SE/4 of Section 17-27S-17W, Kiowa County, Kansas.

Frank E. Stickle  
Frank E. Stickle

C. A. Forrest  
Notary Public

My Commission Expires

RECEIVED  
STATE CORPORATION COMMISSION

JUN 28 1957

PLUGG DIVISION  
Wichita, Kansas  
FILE SEC. 17 T. 21 R. 17W  
BOOK PAGE 23 LINE 3