

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

KIOWA County, Sec. 17 Twp 27 Rge. 17 (XX) (W)

Location as "NE/CNW/SW" or footage from lines SE SE SW/4

Lease Owner Wichita Iron & Metals Corp., Inc.

Lease Name Campbell Well No. 1

Office Address Box 2421 - Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Gas

Date well completed Sept. 26, 19 56

Application for plugging filed Sept. 29, 19 63

Application for plugging approved Sept. 30, 19 63

Plugging commenced Oct. 9, 19 63

Plugging completed Oct. 21, 19 63

Reason for abandonment of well or producing formation depleted and non-productive

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie Elyng

Producing formation Mississippi Depth to top 4669 Bottom 4734 Total Depth of Well 5071 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Well Log enclosed					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pumped mud into formation and well and cemented. Cemented from 265' to 190' with 25 sax cement after rock bridge from 275' to 265'. Mudded from 190' to 35' and ran 10 sax of cement from 35' to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

NOV 12 1963

11-12-63
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Glenn & Smith Pipe Pulling Co.,
Address Box 156, Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Wichita Iron & Metals Corp., Inc. (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God, Wichita Iron & Metals Corp., Inc.

(Signature) By: Ray Stekoll
Ray Stekoll
Box 2421, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of November, 19 63

Evelyn J. North
Evelyn J. North Notary Public.

My commission expires Dec. 22, 1966

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


COPY

Company- AURORA GASOLINE COMPANY
Farm- Campbell No. 1

SEC. 17 T. 27 R. 17W
SE SE SW

Total Depth. 5071'
Comm. 9-5-56 Comp. 9-26-56
Shot or Treated.
Contractor. L. C. Smitherman Drilling Co.
Issued. 12-1-56

County Kiowa KANSAS



Elevation. 2147' RB

Production. 4,150,000 CFGPD

CASING:

8 5/8" @382' w/400 sx cem.
5 1/2" @4767' w/150 sx cem.

Figures indicate Bottom of Formations

surface clay & sand	25	SCOUT TOPS	
sand water	137	Viola	4807
sand w/shale	355	Simpson	4958
red bed	380	Arbuckle	5045
lime shells	382		
lime	390		
red bed	425		
shale & shells	455		
shale & red bed			
w/line strks	1690		
shale & shells red bed	1887		
shale & lime	2170		
shale w/line strks	2205		
Fort Riley lime	2305		
lime w/shale	2400		
lime	2475		
lime w/shale brks	2585		
lime & shale	2661		
lime	2715		
shale & lime	2745		
shale w/line	2915		
shale & lime	3075		
lime w/shale brks	3135		
shale & lime	3435		
shale	3506		
shale & lime	3706		
lime & shale	3788		
lime (Topeka)	3833		
lime & shale	4005		
sand & shale w/line strks	4111		
sand & shale w/line	4120		
lime & shale	4195		
lime (Lansing)	4286		
lime	4306		
lime (Kansas City)	4426		
lime	4469		
lime w/shale brks	4593		
lime & shale	4640		
lime	4669		
Mississippi Chert	4695		
lime (Mississippi)	4734		
Kinderhook shale	4754		
lime & chert	4779		
lime shale & sand	4850		
(Viola)			
lime & shale w/sand	4886		
lime (Conglomerate)	4946		
lime	4986		
sand & shale	5045		
Arbuckle lime	5071		
Total Depth			
SCHLUMBERGER Total Depth	5072		
SCOUT TOPS			
Heebner	3956		
Brown Lime	4105		
Lansing	4121		
Base/Kansas City	4448		
Cherokee Shale	4607		
Mississippi	4669		
Kinderhook Sand	4758		

RECEIVED
STATE CORPORATION COMMISSION

NOV 12 1963

CONSERVATION DIVISION
Wichita, Kansas