

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-097-21,104-0000

LEASE NAME McFadden

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1-21

3960 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 21 TWP. 27 RGE. 17 (N) or (W)

COUNTY Kiowa

LEASE OPERATOR Texas Energies, Inc.

ADDRESS P. O. Box 947 Pratt, Kansas 67124

PHONE#(316) 672-7581 OPERATORS LICENSE NO. 5087

Date Well Completed 4-4-85

Character of Well D&A

Plugging Commenced 4-5-85

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 4-5-85

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom T.D. 4850

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	487	8 5/8"	3-28-85	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Plug well with 140 sxs Lite, 3%cc, 2% gel, as follows: 2130'-50 sxs; 510'-50 sxs; 40'-10 sxs with solid bridge; rathole-15 sxs, mousehole-10 sxs; water well-5 sxs. Job by Dowell. Plug down at 3 p.m. on April 5, 1985. State Pluggger was out of Dodge City, Kansas office.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Wheatstate Oilfield Services, Inc. License No. 5149

Address P. O. Box 329, Pratt, Kansas 67124

STATE OF Kansas COUNTY OF Pratt, ss.

Arnie Little (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so Arnie Little God.

STATE CORPORATION COMMISSION (Signature) Arnie Little

(Address) P. O. Box 329, Pratt, Kansas 67124

SUBSCRIBED AND SWORN TO before me this 24th day of April, 19 85

CONSERVATION DIVISION
Wichita, Kansas



Mary L. Tjaden
Notary Public

My Commission Expires: 3/22/88



Oilfield Services, Inc.

- Rotary Drilling
- Drilling Mud and Chemicals
- Heavy Oil Field Hauling
- Roustabout and Dirt Services
- Well Completion and Servicing Units

DRILLER'S WELL LOG

McFadden #1-21
 C W/2 W/2 NW Sec. 21-27-17W
 Kiowa County, Kansas
 Commenced: 3-27-85
 Completed: 4-5-85
 API #15-097-21,104
 Operator: Texas Energies, Inc.

Depth		Formation	Remarks
From	To		
0	193	Sand	Ran 11 joints (474') new, 24#, 8rd, 8 5/8" surface casing. Set at 487' with 290 sxs Common, 3%cc, 2% gel. Cement did circulate. Job by Dowell. Plug down at 2:15 a.m. on March 28, 1985.
193	497	Clay, Sand	
497	1111	Red Bed, Lime	
1111	4850	Lime, Shale	
		T.D.	

RTD 4850'

Plug well with 140 sxs Lite, 3%cc, 2% gel as follows: 2130'-50 sxs; 510' 50 sxs; 40'-10 sxs with solid bridge; rathole-15 sxs; mousehole-10 sxs; water well-5 sxs. Job by Dowell. Plug down at 3 p.m. on April 5, 1985. State Plugger was out of the Dodge City, Kansas office.

STATE OF KANSAS)
) ss
 COUNTY OF PRATT)

I, the undersigned, being duly sworn on oath, state that the above Driller's Log is true and correct to the best of my knowledge and belief and according to the records of this office.


WHEATSTATE OILFIELD SERVICES, INC.

Arnie Little
 ARNIE LITTLE, VICE-PRESIDENT

RECEIVED

STATE CORPORATION COMMISSION

APR 25 1985



Mary L. Tjaden
 NOTARY PUBLIC

CONSERVATION DIVISION
 Wichita, Kansas

My Commission Expires:

3/22/88