

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

KIOWA

County. Sec. 22 Twp. 27 Rge. 17 (E) W (W)

Location as "NE/CNW%SW%" or footage from lines NE NE SE  
Lease Owner PETROLEUM INC.  
Lease Name GRIMES Well No. 1  
Office Address Route 2, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed January 4 19 57  
Application for plugging filed January 4 19 57  
Application for plugging approved January 4 19 57  
Plugging commenced January 4 19 57  
Plugging completed January 4 19 57

NORTH



Locate well correctly on above  
Section Plat

Reason for abandonment of well or producing formation No Produccible Zones  
If a producing well is abandoned, date of last production None 19       
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M.A. Rives, Box 8, Pratt, Kansas  
Producing formation ----- Depth to top -- Bottom      Total Depth of Well 5030' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8" OD	331'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from      feet to      feet for each plug set.

Mud up with heavy mud to 300', pushed down 1/4 sack hulls to 300' followed by wooden plug. Placed 20 sacks cement through drill pipe on to plug. Mud up to 35' and place 1/4 sack hulls at 35' followed by wooden plug and 10 sacks cement to base of well cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Garvey Drilling Company  
Address Route 2, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
DON SEARLE (employee of owner) or (~~OWNER~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don Searle  
Route 2, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 9th day of January 19 57

My commission expires July 11, 1960

Received Brown  
STATE CORPORATION COMMISSION Notary Public.

PLUGGING  
FILE SEC 22 T. 27 R. 17  
BOOK PAGE 13 LINE 27

JAN 11 1957 1-10-57  
CONSERVATION DIVISION  
Wichita, Kansas

# WELL LOG

COMPANY **PETROLEUM, INCORPORATED**

SEC. **22** T. **27S.** R. **17W**

FARM **Grimes**

NO. **1**

LOC. **NE,NE,SE**

TOTAL DEPTH **5030'**

COUNTY **Kiowa Co., Kansas**

COMM. **December 17, 1956**

COMP. **January 4, 1957**

CONTRACTOR **GARVEY DRILLING COMPANY**



CASING **8 5/8" @ 331' W/250 sax.**

ELEVATION **2134' KB**

PRODUCTION **D & A-**

FIGURES INDICATE BOTTOM OF FORMATIONS

160	Sand & gravel	Anhydrite	1040
250	Shale & sand	Heebner	3936
331	Blud shale	B. Lime	4094
410	Red bed & shale	Kansas City	4109
440	Anhydrite	Mississippi	4636
1040	Shale & sand	Kinderhook Sh	4691
1071	Anhydrite	" Sand	4700
1990	Shale & shells	Viola	4774
2140	Lime		
2305	Lime & shale		
2940	Lime		
3335	Lime & shale		
3535	Lime		
3655	Lime & shale		
3700	Sand		
3835	Lime		
3958	Lime & shale		
3973	Lime		
4163	Lime & shale		
4414	Lime		
4534	Lime & shale		
4577	Lime		
4657	Lime & shale		
4665	Lime		
4685	Shale & chert		
4695	Sand		
4700	Lime		
4762	Lime, shale & s and		
4774	Shale & chert		
4807	Viola chert & shale		
4852	Lime & chert		
4869	Shale & chert		
5030	Lime & s hale		

**RECEIVED**  
STATE CORPORATION COMMISSION

State of KANSAS  
County of BARTON

**PLUGGING**  
FILE SEC 22 T. 27 R. 17W  
BOOK PAGE 131 LINE 27

JAN 13 1957

CONSERVATION DIVISION  
Wichita, Kansas

I, Verne A. Morris of Garvey Drilling Co.

upon oath state that the above and foregoing is a true and correct copy of the log of the #1 Grimes well

*Verne A. Morris*

Subscribed and sworn to before me this 8th day of January 19 57

My Commission Expires: July 11, 1960

*John S. Brown*  
NOTARY PUBLIC

# FIELD ORDER PETROLEUM, INC.

SHOW THIS  
NUMBER  
ON YOUR  
INVOICE

No. 53937

311 East Third Street  
WICHITA 2, KANSAS

Date 1-9, 1957

Please Invoice In Quadruplicate  
Show Lease or Well No. On Invoice  
Retain Original Of Order For Your Records  
Discount Period Will Be Extended Unless Green Copy Of Order Is Attached To Invoice

SUPPLIER

SALES TICKET NO.

ADDRESS

*State Corporation Commission*

*800 Bitting Building  
Wichita, Kansas*

QUANTITY

DESCRIPTION

PRICE

*Assessment*

*\$25.00*

**PAID**  
STATE CORPORATION COMMISSION

*Jan 10 1957*

**PLUGGING**  
FILE SEC 22 T 27 R 17W  
BOOK PAGE 137 LINE 27 VIA

WICHITA DIVISION  
Wichita, Kansas

SHIP MATERIAL TO:

F. O. B.

CARE OF:

DELIVERY DATE REQUESTED:

Lease or Well No:

*Grimes #1*

Signed:

Authorized Agent

Used For:

*Plugging Assessment*

*Jack Perkins*

VENDOR: Attached Copy Must Accompany Invoice.