

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

KIOWA County. Sec. 24 Twp. 27 Rge. 17 (E) W (W)

Location as "NE/CNW/SW" or footage from lines C/SE, SE

Lease Owner Walter Kuhn Drilling Company

Lease Name Tuller Well No. 1

Office Address 726 Union Center Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed May 29, 19 57

Application for plugging filed May 29, 19 57

Application for plugging approved May 29, 19 57

Plugging commenced May 29, 19 57

Plugging completed May 29, 19 57

Reason for abandonment of well or producing formation No productable zone.

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes.

Name of Conservation Agent who supervised plugging of this well M. A. Rives @ Pratt, Kansas

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4788' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	@ 328'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Heavy mud to 325', placed 1/3 sx. hulls, wooden plug, 20 sx. cement through drill pipe.

Heavy mud to 35', placed 1/3 sx. hulls, wooden plug, 10 sx. cement to base of well cellar.

Job complete @ 7:45 PM, 5-29-57

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Garvey Drilling Company

Address R. R. #2 Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss. Verne A. Morris (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Verne A. Morris  
R. R. #2 Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of June, 19 57

RECI  
STATE CORPORATION  
Notary Public.

My commission expires November 12, 1958

JUN 6 X 19 57  
CONSERVATION DIVISION  
Wichita, Kansas

Recd.  
6-6-57

PLUGGING  
SEC 24 T. 27 17W  
BOOK PAGE 17 LINE 0

# WELL LOG

COMPANY ~~WALKER~~ WALTER KUHN DRILLING COMPANY

SEC. 24 T. 27S R. 17W

FARM TULLER

NO. 1

LOC. C/SE, SE


TOTAL DEPTH 4788'

COUNTY Kiowa Co., Kansas

COMM. May 13, 1957

COMP. May 29, 1957

CONTRACTOR GARVEY DRILLING COMPANY



CASING 8 5/8" @ 328' W/260 sax.

ELEVATION 2121' DF

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

160	Sand
270	Sand & shale
330	Sand & red bed.
400	Red bed.
420	Hard sand
540	Sand
783	Shale
1003	Red bed
1032	Anhydrite
1345	Red bed & shale
1490	Salt & shale
2265	Shale & shells
2632	Lime
2763	Lime & shale
2900	Lime
3125	Lime & shale
3822	Lime
3886	Chalky lime
4620	Lime
4651	Lime & chert
4660	Chert
4692	Lime & chert
4700	Lime, shale & chert.
4724	Lime & chert
4729	Chert
4788	Lime & chert
4788	T. D.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 5 X 1957

CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC. 24 T. 27 R. 17  
BOOK PAGE 17 LINE 8

State of KANSAS }  
County of BARTON } ss:

I, Verne A. Morris of Garvey Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the #1 Tuller well

Verne A. Morris

Subscribed and sworn to before me this 3rd day of June 19 57

My Commission Expires: November 12, 1958

Chambers  
NOTARY PUBLIC