

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-095-21,442-0000

LEASE NAME Shehorn

WELL NUMBER 1

SPOT LOCATION NE NE SE

SEC. 2 TWP. 27 RGE. 8 ~~XX~~ or (W)

COUNTY Kingman

Date Well Completed 3-18-84

Plugging Commenced 3-19-84

Plugging Completed 3-19-84

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Jay C. Boyer

ADDRESS Box 511 Hays, KS 67601

PHONE # (913) 625-6967 OPERATORS LICENSE NO. 6139

Character of Well D&A  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Gilbert Toman  
to be filed by

Is ACO-1 filed? operator If not, is well log attached? yes

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3700 <sup>20.25'</sup>

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Bottom Plug: @ 1090' w/35 sacks cement 60/40 pozmix 3% cc thru drill pipe

Next Plug: @ 265' w/ 35 " " " " " " " "

Next Plug: @ 60' w/25 " " " " " " " "

10 sacks cement in Rat Hole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Lobo Drilling Co. License No. \_\_\_\_\_  
Address P.O. Box 877 Great Bend, KS 67530

STATE OF Kansas COUNTY OF Barton, ss.

Ervin Neighbors (employee of operator) or  
(operator) of above-described well, being first duly sworn on oath, says: That  
I have knowledge of the facts, statements, and matters herein contained and  
the log of the above-described well as filed that the same are true and  
correct, so help me God.

RECEIVED  
STATE CORPORATION COMMISSION  
3-26-84  
MAR 26 1984

(Signature) Ervin Neighbors  
(Address) Box 877 Great Bend, KS

SUBSCRIBED AND SWORN TO before me this 21 day of March, 1984  
CONSERVATION DIVISION  
Wichita, Kansas  
Dorothy McLaque  
Notary Public

My Commission expires: 4-29-85

DRILLER'S WELL LOG

DATE COMMENCED: March 14, 1984  
DATE COMPLETED: March 18, 1984

Jay C. Boyer  
Shehorn #1  
NE NE SE  
Sec. 2, T27S, R8W  
Kingman County, Ks.

ELEVATION: 1610 K.B.

0 - 3067' Surface Soil, Shells, Shale  
and Lime  
3067 - 3071' Shale  
3071 - 3094' Lime  
3094 - 3289' Shale  
3289 - 3314' Lime & Shale  
3314 - 3624' Lime  
3624 - 3720' Shale  
3720 - 3790' RTD

FORMATION DATA

Heehner 3067'  
Douglas 3094'  
Br. Lime 3289'  
Lansing 3314'  
Stark Shale 3624'  
RTD 3700'

Surface Pipe: Set new 8-5/8"  
20# pipe @ 314' w/150 sacks  
60/40 pozmix, 2% gel, 3% cc.

A F F I D A V I T

STATE OF KANSAS  
COUNTY OF BARTON) ss

Ervin Neighbors of lawful age, does swear and state that the facts and  
statements herein are true and correct to the best of his knowledge.

*Ervin Neighbors*

Subscribed and sworn to before me this 21 day of March 1984.

My Comm. Expires:

4-29-86

*Dorothy M. Hague*  
Notary Public

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 26 1984  
CORPORATION DIVISION  
Wichita, Kansas