


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Kiowa County. Sec. 36 Twp. 27 Rge. 18 E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines

C NW NW
Lease Owner Cinco Exploration Co.
Lease Name Paulsen #1 Well No.
Office Address Victoria, Texas 77901
Character of Well (Completed as Oil, Gas or Dry Hole)



Date Well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 4/28/80 19
Plugging completed 5/2/80 19
Reason for abandonment of well or producing formation depleted
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Owen
Producing formation Depth to top Bottom Total Depth of Well 4900
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	485	none
				5 1/2"	4890	2493'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Squeezed 5 1/2" casing with 50 sacks common cement. Pumped plug to 4000'. Shot pipe at 3805', 3640', 3435', 3235', 3000', 2805', 2600', 2475', pulled 61 joints.

Squeezed hole with 15 sacks gel, 8 sacks hulls, 10 sacks gel. Released plug and displaced with 125 sacks 50-50 pozmix, 4% gel and 3% cc.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS (Address)

SUBSCRIBED AND SWORN TO before me this 6th day of May, 19 80



Margaret Melcher
Notary Public.

My commission expires

RECEIVED
CONSERVATION COMMISSION
MAY - 8 1980
5-8-80
CONSERVATION DIVISION
Wichita, Kansas

KANSAS DRILLERS LOG

COMPANY Cinco Exploration Co.

SEC 36 - 27S. 18W
T6E 660' FNL & 600' FNL

FARM Paulsen

NO. 1

COUNTY Kiowa

ROTARY TOTAL DEPTH 4900'
COMM August 8, 1978
CONTRACTOR H-30, Inc.
ISSUED August 25, 1978

COMP August 19, 1978

CASING

10 3/4"
8 5/8" 485' cemented w/400 sxs cement
5 1/2" 4890' cemented w/200 sxs cement
4 1/2"

ELEVATION 2169 D.F.

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand	145'
Shale and Lime	355'
Shale and Anhydrite	486'
Sand and Red Bed	1225'
Shale and Lime	4330'
Lime and Shale	4760'
Chert and Lime	4900'
Rotary Total Depth	4900'

RECEIVED
STATE CORPORATION COMMISSION
APR - 8 1980
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Dean Britting
Dean Britting

State of Kansas }
County of Sedgwick } ss:

Subscribed and Sworn to before me a Notary Public in and for said county and state

WILLISON
this 25th. day of August 25, 1978.

Elsie Willison
Elsie Willison-Notary Public

My Commission Expires:

July 25, 1982