

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Kiowa SEC. 30 TWP. 27S RGE. 18 E/W
Location as in quarters or footage from lines:
620' from south line, 1730' from east line

		30	
		x	

Locate Well
correctly on above
Section Platt.

Lease Owner TGT Petroleum Corp.
 Lease Name Rice "D" Well No. 2-C
 Office Address 209 E. William - Wichita, Ks. 67202
 Character of Well (Completed as Oil, Gas or Dry Hole): Core Hole
 Date Well Completed 12-20-82
 Application for plugging filed 12-20-82
 Plugging commenced 9:35 AM 12-21-82
 Plugging completed 9:55 AM 12-21-82
 Reason for abandonment of well or producing formation Finish logging
 Was permission obtained from the Conservation Division or it's Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant
 Producing formation _____ Depth to top _____ bottom _____ T.D. 1224
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
		GL	202'	5 1/2"	202'	Cemented surface casing

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Halliburton hook-up to 5 1/2" surface casing, mix & pump in 2 sacks gel, 2 sacks hulls, followed by 65 sacks common cement, 2% gel, 3% cc. Then pump in 1/4 bbl. clear water to clear valve, swedge & landing sub. Shut in, leaving hole cemented from 10' to 800'. Pump down pressure 400 PSI. Shut in pressure 300

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor TGT Petroleum Corp.

STATE OF Kansas COUNTY OF Sedgwick, ss.
B. Lynn Herrington (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
 RECEIVED STATE CORPORATION COMMISSION
 DEC 27 1982
 (Signature) B. Lynn Herrington
209 E. William - Wichita, Ks (Address)

CONSERVATION DIVISION
SUBSCRIBED AND SWORN TO before me this 23rd day of December, 1982

My Commission expires: 5-17-85

Judith K. Moser
 Judith K. Moser Notary Public.
 JUDITH K. MOSER
 NOTARY PUBLIC
 STATE OF KANSAS
 My Appt. Exp. May 17, 1985