

STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

	O		

Locate well correctly on above
Section Plat

Reno County. Sec. 12 Twp. 25 Rge. 10 (E) (W)
Location as "NE/CNW/SW" or footage from lines NE NE NW
Lease Owner Schermerhorn Oil Corporation
Lease Name Morris Well No. 1
Office Address 714 First National Bldg., Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Went dry
Date well completed 5-19-54
Application for plugging filed 11-8-54
Application for plugging approved 11-8-54
Plugging commenced 11-8-54
Plugging completed 11-12-54
Reason for abandonment of well or producing formation Not producing enough oil
to pay
If a producing well is abandoned, date of last production Oct. 1, 1954
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well Red Horner
Producing formation Chat Depth to top 3889 Bottom 3904 Total Depth of Well 4347 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	240	8 5/8	Cemented	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

4347 to 3787 Cement
3787 to 300 Mud
300 to bottom celler cement

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor
Address

STATE OF Oklahoma, COUNTY OF Tulsa, ss.
Don E. Burkitt (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)


714 First National Bldg, Tulsa, Oklahoma
(Address)

SUBSCRIBED AND SWORN to before me this 6th day of December, 1954

My commission expires 10-20-57.

Notary Public.

24-7368-6 3-53-20M



12-7-54

MORRIS #1
N/2 NE and E/2 NW Section 12-25S-10W
Reno County, Kansas


Drilling started 4-15-54
Drilling completed 5-5-54
8 5/8" 24# Casing Cemented @ 240'
5 1/2" 14# Casing Cemented @ 3984'

From	To	Formation	Remarks
0	95	Sand	
95	240	Red Bed	240' 8 5/8" Cemented @ 240'
240	435	Red Bed	
435	450	Anhydrite	
450	1300	Shale & Shells	
1300	1680	Lime & Shale	
1680	1925	Lime	
1925	2912	Lime & Shale	
2912	3233	Lime	
3233	3351	Lime & Shale	
3351	3786	Lime	
3786	3834	Lime and Shale	
3834	3896	Lime	
3896	3932	Chert	
3932	3946	Chert and Lime	
3946	4129	Shale and Lime	
4129	4232	Lime	
4232	4256	Sand and Shale	
4256	4301	Shale & Lime	
4301	4347	Lime	T.D. 4347' 3984' 5 1/2" Casing cemented w/100 sacks/

This is a certified true copy of the Driller's Log as shown on the daily drilling reports.


BADGER DRILLERS, INC.

Subscribed and sworn to before
me this 6th day of September, 1954.


Notary Public

SECTION

12-7-54

