

1052384

TO: STATE CORPORATION COMMISSION

API NUMBER 15-047-20,607-00-00
NW SW SE SEC. 13, T 24 S, R 18 W

CONSERVATION DIVISION - PLUGGING SECTION 990 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2310 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME CHALK WELL # 2-13

TECHNICIAN'S PLUGGING REPORT

4/18

COUNTY EDWARDS 149.50

OPERATOR LICENSE # 5056

WELL TOTAL DEPTH 4600 FEET

OPERATOR: F.G. HOLL COMPANY, LLC PRODUCTION CSG: SIZE 4 1/2" @ 4599' WITH 175 SX

NAME AND PO BOX 780167 SURFACE CASING: SIZE 8 5/8" @ 259' WITH 225 SX

ADDRESS WICHITA, KS 67278-0167

ABANDONED OIL WELL X GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR QUALITY WELL SERVICE LICENSE NUMBER 31925

ADDRESS 249 EAST BETH DR. STERLING, KS 67579

COMPANY TO PLUG AT: HOUR: 1:00 PM DAY: 18 MONTH: 04 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM RICHARD MCNTYRE

(COMPANY NAME) QUALITY WELL SERVICE (PHONE) 316-727-3410

WERE: PERFS AT 3872-74

1ST PLUG SANDED TO 4280' AND 4 SX CEMENT. 2ND PLUG AT 1200' WITH 10 SX GEL & 50 SX CEMENT

3RD PLUG AT 280' WITH 50 SX CEMENT. 4TH PLUG AT 40' WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 3:16 PM DAY: 18 MONTH: 04 YEAR: 2000

ACTUAL PLUGGING REPORT

1ST PLUG SANDED TO 4280' AND 4 SX CEMENT. 2ND PLUG AT 1200' WITH 10 SX GEL & 50 SX CEMENT

3RD PLUG AT 280' WITH 50 SX CEMENT. 4TH PLUG AT 40' WITH 10 SX CEMENT

INVOICED

DATE 4/25/00

INV. NO. 061642

RECEIVED STATE CORPORATION COMMISSION

APR 24 2000

CONSERVATION DIVISION Wichita, Kansas

REMARKS: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. RECOVERED 2000' OF 4 1/2" CASING (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Richard W. Lacey (TECHNICIAN) FORM CP-2/3

Handwritten signature and initials in a circle.