

1070141

TO: STATE CORPORATION COMMISSION

API NUMBER 15-047-00363-00-00  
SW NE NW SEC. 12, T 25 S, R 16 W

CONSERVATION DIVISION - PLUGGING SECTION 990 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1650 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME E C SMITH WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY EDWARDS 141.38

OPERATOR LICENSE # 31021

WELL TOTAL DEPTH 4350 FEET

OPERATOR: CASTELLI EXPLORATION, INC. PRODUCTION CSG: SIZE 5 1/2" @ 4349' WITH 150 SX

NAME AND ADDRESS 9500 WESTGATE DR, SUITE 101 SURFACE CASING: SIZE 8 5/8" @ 1035' WITH 600 SX

ADDRESS OKLAHOMA CITY, OK 73162

ABANDONED OIL WELL GAS WELL X INPUT WELL INJ WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE, INC LICENSE NUMBER 31528

ADDRESS PO BOX 467, CHASE, KS 67524-0209

COMPANY TO PLUG AT: HOUR: 9:35 AM DAY: 01 MONTH: 08 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM MIKE KELSO

(COMPANY NAME) MIKE'S TESTING & SALVAGE (PHONE) 316-938-2945

WERE: PERFS AT 4215-87. CIBP @ 3950, PERFS AT 3848-55

SAND BACK TO 3800', 5 SX CEMENT WITH BAILER. 1ST PLUG AT 1050' WITH 50 SX CEMENT.

2ND PLUG AT 400' WITH 40 SX CEMENT. 3RD PLUG AT 0-40' WITH 10 SX CEMENT. 12 SX GEL FOR SPACERS.

PLUGGING PROPOSAL RECEIVED BY SCOTT ALBERG

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 11:10 AM DAY: 01 MONTH: 08 YEAR: 2000

ACTUAL PLUGGING REPORT

SAND BACK TO 3800', 5 SX CEMENT WITH BAILER. 1ST PLUG AT 1050' WITH 50 SX CEMENT.

2ND PLUG AT 400' WITH 40 SX CEMENT. 3RD PLUG AT 0-40' WITH 10 SX CEMENT. 12 SX GEL FOR SPACERS.

RECEIVED STATE CORPORATION COMMISS

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2223' OF 5 1/2" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

AUG 4 2000

I (DID) OBSERVE THIS PLUGGING

INVOICED  
SIGNED  
DATE 8/10/00  
INV. NO. 1060340

(TECHNICIAN)

CONSERVATION DIVISION Wichita, Kansas

FORM CP-2/3

Handwritten signature