

1052409

TO: STATE CORPORATION COMMISSION

API NUMBER 15-047-20,052 - 00-00
C SE SW SEC. 15, T 25 S, R 16 W

CONSERVATION DIVISION - PLUGGING SECTION 660 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1650 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME JULIAN A WELL # 3

TECHNICIAN'S PLUGGING REPORT 7/28

COUNTY EDWARDS 144, 66

OPERATOR LICENSE # 5427

WELL TOTAL DEPTH 4451 FEET

OPERATOR: D.R. LAUCK OIL CO., INC PRODUCTION CSG: SIZE 5 1/2" @ 4451' WITH 140 SX

NAME AND 221 S BROADWAY, SUITE 400 SURFACE CASING: SIZE 8 5/8" @ 294' WITH 225 SX

ADDRESS WICHITA, KS 67202

ABANDONED OIL WELL X GAS WELL _____ INPUT WELL _____ INJ WELL _____ D/A _____

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE, INC LICENSE NUMBER 31529

ADDRESS PO BOX 467, CHASE, KS 67524-0209

COMPANY TO PLUG AT: HOUR: 9:00 AM DAY: 28 MONTH: 07 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM MIKE KELSO

(COMPANY NAME) MIKE'S TESTING & SALVAGE (PHONE) 316-938-2945

WERE: PERFS AT 4330-4340

1ST PLUG SAND TO 4250' & 5 SX CEMENT. SPOT PLUGS THROUGH CASING WHILE PULLING.

RECEIVED
STATE CORPORATION COMMISSION

2ND PLUG AT 1050' WITH 10 SX GEL - 50 SX CEMENT DISPLACED WITH 2 SX GEL.

AUG - 7 2000

3RD PLUG AT 325' WITH 50 SX CEMENT. 4TH PLUG AT 40' WITH 10 SX CEMENT.

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART _____ NONE _____

OPERATIONS COMPLETED: HOUR: 11:30 AM DAY: 28 MONTH: 07 YEAR: 2000

ACTUAL PLUGGING REPORT _____

1ST PLUG SAND TO 4250' & 5 SX CEMENT. SPOT PLUGS THROUGH CASING WHILE PULLING.

2ND PLUG AT 1050' WITH 10 SX GEL - 50 SX CEMENT DISPLACED WITH 2 SX GEL.

3RD PLUG AT 325' WITH 50 SX CEMENT 4TH PLUG AT 40' WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2200' OF 5 1/2" CASING.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

INVOICED

DATE 8/10/00 SIGNED Richard W. Lacey
(TECHNICIAN)

WVV. NO. 1060351

FORM CP-2/3