

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-047-20173-00-00  
Spot: CSESW Sec/Twnshp/Rge: 19-25S-16W  
660 feet from S Section Line, 1980 feet from W Section Line  
Lease/Unit Name: RUSSELL A Well Number: 1  
County: EDWARDS Total Vertical Depth: 4797 feet

Operator License No.: 5427  
Op Name: LAUCK, D.R. OIL CO., INC.  
Address: 221 S. BROADWAY, STE 400  
WICHITA, KS 67202

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 329 WITH 225 SX CMT  
Production: Size 5.5 feet: 4783 WITH 150 SX CMT  
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 03/30/2001 11:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (316) 938-2537

Proposed Plugging Method: SAND TO 4300' & 5 SX CMT. 1ST PLUG AT 1050' WITH 50 SX CMT. 2ND PLUG AT 350' WITH 50 SX CMT. 3RD PLUG AT 0-40' WITH 20 SX CMT. USE 10 SX GEL FOR SPACER.

155.90

Plugging Proposal Received By: SCOTT ALBERG  
Date/Time Plugging Completed: 03/30/2001 12:15 PM

Witness Type: Plugging Operations 100% Witnessed (Complete)  
KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PERFS AT 4354-68, 4380-88, 4413-20'. SANDED BACK TO 4270' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH 5 1/2" CASING. LOAD HOLE WITH GEL. 1ST PLUG AT 1050' WITH 50 SX CMT. 2ND PLUG AT 350' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

INVOICED  
DATE 4-5-01  
2001061591

RECEIVED  
STATE CORPORATION COMMISSION

APR - 5 2001

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2220' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed

Stephen J. Pfeifer  
(TECHNICIAN)

APR 02 2001

Form 213