

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-20430-00-00
Spot: CN2SESE Sec/Twnshp/Rge: 8-25S-17W
4290 feet from S Section Line, 4620 feet from E Section Line
Lease/Unit Name: QUERFELD Well Number: 1
County: EDWARDS Total Vertical Depth: 4600 feet

Operator License No.: 5086
Op Name: PINTAIL PETROLEUM, LTD.
Address: 225 NORTH MARKET, STE 300
WICHITA, KS 67202

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 254 WITH 225 SX CMT
Production: Size 4.5 feet: 4594 WITH 125 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 03/23/2001 10:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOE MAES Company: QUALITY WELL SERVICE, INC. Phone: (316) 278-2026

Proposed Plugging Method: SAND TO 4395' & 4 SX CMT. 1ST PLUG AT 1150' WITH 50 SX CMT. 2ND PLUG AT 280' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. USE 15 SX GEL FOR SPACER.

149.50

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 03/23/2001 11:45 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PBTD 4491'. PERFS AT 4445-57'. SANDED BACK TO 4395' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH 4 1/2" CASING. LOAD HOLE WITH GEL. 1ST PLUG AT 1140' WITH 50 SX CMT. 2ND PLUG AT 280' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

INVOICED
DATE 4-5-01
INV. NO. 2001061580

RECEIVED
STATE CORPORATION COMMISSION
APR - 5 2001
CONSERVATION DIVISION
Wichita, Kansas

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2318' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed Stephen J. Pfeifer
(TECHNICIAN)

MAR 29 2001

REC'D
MAR 29 2001