

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-047-20985-00-00  
Spot: NESESE Sec/Twnshp/Rge: 25-25S-17W  
4290 feet from N Section Line, 4950 feet from W Section Line  
Lease/Unit Name: INGRAHAM - A Well Number: 2  
County: EDWARDS Total Vertical Depth: 4690 feet

Operator License No.: 5086  
Op Name: PINTAIL PETROLEUM, LTD.  
Address: 225 NORTH MARKET, STE 300  
WICHITA, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 8.625 feet: 400 WITH 200 SX CMT  
Production: Size 4.5 feet: 4699 WITH 125 SX CMT  
Liner: Size \_\_\_\_\_ feet:

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/21/2001 2:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: JOE MAES Company: QUALITY WELL SERVICE, INC. Phone: (316) 727-3410

Proposed Plugging Method: SAND TO 4380' & 4 SX CMT. 1ST PLUG AT 1140' WITH 50 SX CMT. 2ND PLUG AT 430' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

152.43

Plugging Proposal Received By: STEVE PFEIFER Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 03/21/2001 3:30 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PBTD 4452'. PERFS AT 4430-45'. SAND TO 4380' WITH 4 SX CMT ON TOP. 1ST PLUG PULL CASING TO 1140' PUMP IN 10 SX GEL & 50 SX CMT. PUMP IN 5 SX GEL. 2ND PLUG PULL TO 430' SPOT 50 SX CMT. 3RD PLUG PULL TO 40' FILL TO SURFACE WITH 10 SX CMT. STAYED FULL.

**INVOICED**  
DATE 3-30-01  
INV. NO. 2001061558

RECEIVED  
STATE CORPORATION COMMISSION

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2313' OF 4 1/2" CASING.

Plugged through: CSG

MAR 26 2001  
3-26-01  
CORP. COMMISSION

District: 01

Signed

  
(TECHNICIAN)

MAR 22 2001

