

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-20548-00-00
Spot: CNWSWSW Sec/Twnshp/Rge: 1-26S-16W
990 feet from S Section Line, 330 feet from W Section Line
Lease/Unit Name: BISEL Well Number: 2
County: EDWARDS Total Vertical Depth: 4446 feet

Operator License No.: 31000
Op Name: PRATER OIL & GAS OPERATIONS, INC.
Address: 906 WILLIAM WAY
PRATT, KS 67124

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 376 WITH 300 SX CMT
Production: Size 5.5 feet: 4433 WITH 250 SX CMT
Liner: Size _____ feet:

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/27/2001 1:45 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (316) 938-2537

Proposed Plugging Method: SAND TO 3750' & 5 SX CMT. 1ST PLUG AT 1050' WITH 50 SX CMT. 2ND PLUG AT 400' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. USE 15 SX GEL FOR SPACER.

144.50

Plugging Proposal Received By: STEVE MIDDLETON Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 03/27/2001 3:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PBTD 4378'. PERFS AT 3923-27, 4042-47, 4354-70'. SANDED BACK TO 3750' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH 5 1/2" CASING. LOAD HOLE WITH GEL. 1ST PLUG AT 1050' WITH 50 SX CMT. 2ND PLUG AT 400' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

INVOICED
DATE 4-5-01
NO. 2001061576

RECEIVED
STATE CORPORATION COMMISSION
APR - 5 2001
CONSERVATION DIVISION
Wichita, Kansas

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2320' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed Stephen J. Pfeifer
(TECHNICIAN)

APR 02 2001

Form CP-18

MP #