

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-20551-00-01
Spot: N2NWNW Sec/Twnshp/Rge: 35-26S-17W
4770 feet from S Section Line, 4620 feet from E Section Line
Lease/Unit Name: CROCKETT Well Number: 4
County: EDWARDS Total Vertical Depth: 4450 feet

Operator License No.: 5420
Op Name: WHITE & ELLIS DRILLING, INC.
Address: PO BOX 48848
WICHITA, KS 67201

Conductor Pipe: Size feet: 144.63
Surface Casing: Size 8.625 feet: 362 WITH 350 SX CMT
Production: Size 4.5 feet: 4452 WITH 100 SX CMT
Liner: Size feet:

Well Type: EOR UIC Docket No: E24746.2 Date/Time to Plug: 02/07/2002 12:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: CIBP @ 4265' WITH 2 SX CMT ON TOP. 1ST PLUG AT 1130' WITH 50 SX CMT. 2ND PLUG AT 390' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. USE 15 SX GEL FOR SPACER.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 02/07/2002 2:05 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PBTD 4452'. PERFS AT 4372-4374'. SET CIBP @ 4265' & 2 SX CMT ON TOP OF PLUG WITH DUMP BAILER. SPOTTED PLUGS THROUGH CASING. 1ST PLUG AT 1130' WITH 15 SX GEL - 50 SX CMT. 2ND PLUG AT 390' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2440' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED
FEB 12 2002
KCC WICHITA

INVOICED
DATE Feb 13-02
INV. NO. 2002061376
FEB 08 2002
AP

Form CP-2/3