

1052390

TO: STATE CORPORATION COMMISSION

API NUMBER 15-047-21,092 - 00-00
SW SE SE SEC. 1, T 24 S, R 17 W

CONSERVATION DIVISION - PLUGGING SECTION 330 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 990 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME BRENSING "C" WELL # 3-1

TECHNICIAN'S PLUGGING REPORT 4/24 COUNTY EDWARDS 14268

OPERATOR LICENSE # 5056 WELL TOTAL DEPTH 4390 FEET

OPERATOR: F.G. HOLL COMPANY, LLC PRODUCTION CSG: SIZE 4 1/2" @ 4385' WITH 225 SX

NAME AND PO BOX 780167 SURFACE CASING: SIZE 8 5/8" @ 255' WITH 210 SX

ADDRESS WICHITA, KS 67278-0167

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR QUALITY WELL SERVICE LICENSE NUMBER 31925

ADDRESS 249 BETH DRIVE, STERLING, KS 67579

COMPANY TO PLUG AT: HOUR: 1:00 PM DAY: 24 MONTH: 04 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM RICHARD MCINTYRE

(COMPANY NAME) QUALITY WELL SERVICE (PHONE) 316-727-3410

WERE: PERFS AT 4330-34

SANDED TO 4276' AND 4 SX CEMENT WITH DUMP BAILER. PUMPED PLUGS THROUGH CASING WHILE

PULLING. 1ST PLUG AT 1200' WITH 10 SX GEL - 50 SX CEMENT. 2ND PLUG AT 290' WITH 50 SX

CEMENT. 3RD PLUG AT 40' WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 3:01 PM DAY: 24 MONTH: 04 YEAR: 2000

ACTUAL PLUGGING REPORT

SANDED TO 4276' AND 4 SX CEMENT WITH DUMP BAILER. PUMPED PLUGS THROUGH CASING WHILE

PULLING. 1ST PLUG AT 1200' WITH 10 SX GEL - 50 SX CEMENT. 2ND PLUG AT 290' WITH 50 SX

CEMENT. 3RD PLUG AT 40' WITH 10 SX CEMENT.

RECEIVED STATE CORPORATION COMMISSION

REMARKS: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. RECOVERED 2231' OF 4 1/2" CASING. MAY 4 2000

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

INVOICED SIGNED

Richard W. Lacey (TECHNICIAN)

CONSERVATION DIVISION Wichita, Kansas

DATE 5/9/00

FORM CP-2/3

WELL NO. 61694

Handwritten signature 'R' in a circle