

1052419

15-047 - 20588-0000

TO: STATE CORPORATION COMMISSION

API NUMBER DRILLED 11/06/79  
C N/2 NW SEC. 33, T 24 S, R 16 W

CONSERVATION DIVISION - PLUGGING SECTION 1320 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 660 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME LARAMORE WELL # 33

TECHNICIAN'S PLUGGING REPORT

COUNTY EDWARDS

8/15  
\$142.48

OPERATOR LICENSE # 32005

WELL TOTAL DEPTH 4384 FEET

OPERATOR: KERA OIL

PRODUCTION CSG: SIZE 4 1/2" @ 4423' WITH 150 SX

NAME AND PO BOX 463

SURFACE CASING: SIZE 8 5/8" @ 324' WITH 275 SX

ADDRESS GREAT BEND, KS 67530

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR DS&W WELL SERVICING LICENSE NUMBER 6901

ADDRESS PO BOX 231 CLAFLIN, KS 67525

COMPANY TO PLUG AT: HOUR: 11:00 AM DAY: 15 MONTH: 08 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM BRIAN

(COMPANY NAME) DS&W WELL SERVICING (PHONE) 316-587-3361

WERE: PERFS AT 4302-04 & 4308-28

SANDED TO 4250' AND 4 SX CEMENT. SPOTTED PLUGS THROUGH CASING WHILE PULLING CASING.

1ST PLUG AT 1050' WITH 10 SX GEL - 50 SX CEMENT. 2ND PLUG AT 350' WITH 50 SX CEMENT.

3RD PLUG AT 40' WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 12:05 PM DAY: 15 MONTH: 08 YEAR: 2000

ACTUAL PLUGGING REPORT

SANDED TO 4250' AND 4 SX CEMENT. SPOTTED PLUGS THROUGH CASING WHILE PULLING CASING.

1ST PLUG AT 1050' WITH 10 SX GEL - 50 SX CEMENT. 2ND PLUG AT 350' WITH 50 SX CEMENT.

3RD PLUG AT 40' WITH 10 SX CEMENT.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 22 2000

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2200' OF 4 1/2" CASING.

CONSERVATION DIVISION  
Wichita, Kansas

I (DID) OBSERVE THIS PLUGGING.

INVOICED

DATE 8/24/00 SIGNED

Richard W. Lacey  
(TECHNICIAN)

FORM CP-2/3

WV. NO. 2001060520

Handwritten initials and signature in a circle.