

1041408

TO: STATE CORPORATION COMMISSION

API NUMBER 15-047-20,613 - 00 - 00
NE SEC. 30, T 24 S, R 16 W

CONSERVATION DIVISION - PLUGGING SECTION 1050 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 430 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME BREITENBACH "B" WELL # 1-30

TECHNICIAN'S PLUGGING REPORT

COUNTY EDWARDS

144.30

OPERATOR LICENSE # 5056

WELL TOTAL DEPTH 4440 FEET

OPERATOR: F.G. HOLL COMPANY, LLC PRODUCTION CSG: SIZE 4 1/2" @ 4439' WITH 175 SX

NAME AND PO BOX 780167 SURFACE CASING: SIZE 8 5/8" @ 251' WITH 200 SX

ADDRESS WICHITA, KS 67278-0167

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR QUALITY WELL SERVICE LICENSE NUMBER 31925

ADDRESS 249 EAST BETH DR. STERLING, KS 67579

COMPANY TO PLUG AT: HOUR: 9:15 AM DAY: 17 MONTH: 07 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM RICHARD MCNTYRE

(COMPANY NAME) QUALITY WELL SERVICE (PHONE) 316-727-3410

WERE: PERFS AT 4338-4342 & 4340-4344

SANDED BACK TO 4287' AND PUT 4 SX CEMENT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER.

LOAD HOLE WITH GEL. SPOT PLUGS THROUGH 4 1/2" CASING. 1ST PLUG AT 1050' WITH 50 SX CEMENT.

2ND PLUG AT 280' WITH 50 SX CEMENT. 3RD PLUG AT 40' WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 10:15 AM DAY: 17 MONTH: 07 YEAR: 2000

ACTUAL PLUGGING REPORT

SANDED BACK TO 4287' AND PUT 4 SX CEMENT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER.

LOAD HOLE WITH GEL. SPOT PLUGS THROUGH 4 1/2" CASING. 1ST PLUG AT 1050' WITH 50 SX CEMENT.

2ND PLUG AT 280' WITH 50 SX CEMENT. 3RD PLUG AT 40' WITH 10 SX CEMENT.

RECEIVED
AUG - 8 - 2000
8-8-00

REMARKS: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. RECOVERED 2332' OF 4 1/2" CASING.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

INVOICED
DATE 8/10/00
INV. NO. 1060352

SIGNED Stephen J. Pfeifer
(TECHNICIAN) FORM CPT 2/3

Handwritten initials and signature