

To: 1 040755  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

5-20

API NUMBER 15- 151-21,830A  
C SE SE , SEC. 31 , T 27 S, R 15 W/X

TECHNICIAN'S PLUGGING REPORT

Operator License # 6050  
Operator: Kelso Casing Pulling, Inc.  
Name & Address P.O. Box 347  
Chase, KS 67524-0347

660 feet from S section line  
660 feet from E section line  
Lease Name Bryant A Well # 1  
County Pratt  
Well Total Depth 4760 154.70 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 402

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050  
Address P.O. Box 347, Chase, KS 67524-0347

Company to plug at: Hour: 9 a.m. Day: 20 Month: 5 Year: 19 93

Plugging proposal received from Vernon Duntz  
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

Work: 4 1/2" at 4730' w/100 sx cement, Perfs at 4591-95'  
1st plug sand back to 4540' and dump 4 sx cement on top of sand bridge through bailer,  
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8"  
wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 10 a.m. Day: 20 Month: 5 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 4540' and dumped 4 sx cement on top of sand  
bridge through bailer,  
2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx  
gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.  
Maximum pressure 600 psi and shut in 300 psi.

RECEIVED  
5-25-93  
MAY 25 1993

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3600' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

observe this plugging.

INVOICED  
DATE JUN 01 1993  
INV. NO. 32284

Signed *Stephen J. Plesner*  
(TECHNICIAN)

CONSERVATION DIVISION  
Wichita, Kansas