

1030680

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 187-20,404-0000

C NW NE, SEC. 25, T 27 S, R 41 W/E
4620 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5652

Lease Name Lane Well # 1-25

Operator: Mustang Drilling & Exploration, Inc.
Name & Address: P. O. Box 1609
Great Bend, KS 67530

County Stanton 176.05

Well Total Depth 5417 Mississippi feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1715

Abandoned Oil Well Gas Well Input Well SWD Well D&A x

Other well as hereinafter indicated

Plugging Contractor Mustang Drilling & Exploration, Inc. License Number 5652

Address P. O. Box 1609, Great Bend, KS 67530

Company to plug at: Hour: 2:00 pm Day: 22 Month: March Year: 19 86

Plugging proposal received from Bill Nelson

(company name) Mustang (phone) 316-792-7323

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1714-28' Elevation N/A

1st plug at 3200' with 50 sx cement 4th plug at 690' with 25 sx cement

2nd plug at 2600' with 50 sx cement 5th plug hulls - plug at 40' -- cement to surface with 10 sx cement

3rd plug at 1700' with 50 sx cement

7th plug to circulate rat hole with 15 sx cement

8th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None x

Operations Completed: Hour: 7:00 pm Day: 22 Month: March Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 3200' with 50 sx cement, 2nd plug at 2600' with 50 sx cement, 3rd plug at 1740' with 50 sx cement, 4th plug at 690' with 25 sx cement, 5th

& 6th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement,

7th plug to circulate rat hole with 15 sx cement

Remarks: Used 60/40 Pozmix 6% gel by Dowell.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE APR 1 1986

STATE CORPORATION COMMISSION Signed Steve Durrant (TECHNICIAN)

INV NO 13213

MAR 31 1985 3-31-86

CONSERVATION DIVISION

FORM CP-2/3 Rev. 01-84

CARD MUST BE TYPED

State of Kansas
NOTICE OF INTENTION TO DRILL
(see rules on reverse side)

CARD MUST BE SIGNED

Starting Date March 14, 1986
month day year

API Number 15- 187-20,404

OPERATOR: License # 5652
Name Mustang Drilling & Exploration, Inc.
Address P.O. Box 1609
City/State/Zip Great Bend, KS 67530
Contact Person James Meroney
Phone 316-792-7323

C NW NE Sec. 25 Twp. 27 S, Rg. 141 East
4620 Ft. from South Line of Section
1980 Ft. from East Line of Section
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5652
Name Mustang Drilling & Exploration, Inc.
City/State Great Bend, KS 67530

Nearest lease or unit boundary line 660 feet
County Stanton
Lease Name Lane Well # 1-25
Ground surface elevation 660 feet MSL
Domestic well within 330 feet: yes no
Municipal well within one mile: yes no
Surface pipe by Alternate: 1 2
Depth to bottom of fresh water 325
Depth to bottom of usable water 650
Surface pipe planned to be set 1700
Projected Total Depth 5450 feet
Formation Mississippi

Well Drilled For: Well Class: Type Equipment:
 Oil SWD Infield Mud Rotary
 Gas Inj Pool Ext. Air Rotary
 OWWO Expl Wildcat Cable

If OWWO: old well info as follows:
Operator _____
Well Name _____
Comp Date _____ Old Total Depth _____

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
YES cementing will be done immediately upon setting production casing.
Date 1-9-86 Signature of Operator or Agent [Signature] Title Exploration Manager

For KCC Use:
Conductor Pipe Required _____ feet; Minimum Surface Pipe Required _____ feet per Alt. 1
This Authorization Expires 7-9-86 Approved By [Signature]

Bill Nelson
PUSHER Bill Nelson
TD 5417 FORMATION Mississippi
SURFACE PIPE 8 3/8 @ 1715
ANHYDRITE 1214-28 ELEVATION 3321
STARTING TIME & DATE 2:00am 3/22/86
COMPLETION TIME & DATE 7:00am 3/22/86
1st PLUG @ 3200 FT. W/ 50 SX
2nd PLUG @ 2600 FT. W/ 50 SX
3rd PLUG @ 1740 FT. W/ 50 SX
4th PLUG @ 690 FT. W/ 25 SX
40 SBP+10SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ _____ SX
WATER WELL PLUGGED W/ _____ SX
CEMENT COMPANY Rowell
TECHNICIAN 60/40 c90ge 1

STATE COMMISSION
MAR 31 1986
CONSERVATION DIVISION
Winchita, Kansas