

To: 1 020416
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

10-25 API NUMBER 15- NA 15-187-00137-0000 250
SW-SW NE, SEC. 33, T. 27 S, R. 39 W/4E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5952
Operator: Amoco Production Company
Name & Address: P.O. Box 800, Rm. 2444
Denver, CO 80201

2740 feet from S section line
2540 feet from E section line
Lease Name Baughman GU D Well # 1
County Stanton 8/25
Well Total Depth 2500 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 10 3/4 feet 676

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Midwest Casing Pullers License Number 6497
Address Box F, Sublette, KS

Company to plug at: Hour: 11 a.m. Day: 25 Month: 10 Year: 19 91

Plugging proposal received from Ed Eves
(company name) Midwest Casing Pullers (phone) 316-675-8349

were: 7" at 2293' w/350 sx cement, 5 1/2" slotted liner 2264-2500'
1st plug set CIBP at 2200' with 3 sx cement on top,
2nd plug pull to 700' and spot 75 sx cement,
3rd plug pull to 500' and spot 50 sx cement,
4th plug pull to 40' and spot 20 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 4 p.m. Day: 25 Month: 10 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug set CIBP at 1920' with 2 sx cement on top,
2nd plug shot pipe off at 660', circulated 200 sx cement to surface down 7".

RECEIVED
STATE CORPORATION COMMISSION
OCT 30 1991
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used common cement by Midwest. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 11-13-91
INV. NO. 33690

Signed Steve R. Barlow (TECHNICIAN)