

To: 1 020700 9-1  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-Drill completion date 5/16/60

App. SW NE SEC. 6, T 27 S, R 34 W EX  
3550 feet from S section line

1920 feet from E section line

Lease Name Pleasant Prairie Unit Well # 56

County Haskell

Well Total Depth 5187 168.57 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 800

TECHNICIAN'S PLUGGING REPORT

Operator License # 5293

Operator: Helmerich & Payne, Inc.

Name & Address P.O. Box 558

Garden City, KS 67846

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Helmerich & Payne, Inc. License Number 5293

Address P.O. Box 558, Garden City, KS 67846

Company to plug at: Hour: 10:30 a.m. Day: 31 Month: 8 Year: 19 93

Plugging proposal received from James Ford

(company name) Helmerich & Payne, Inc. (phone) 316-276-3693

were: 5 1/2" at 5180' w/650 sx cement, PBSD 5143', Perfs at 4986-4992, 5047-57, 5107-24'

1st plug set CIBP at 4930' with 2 sx cement on top,

2nd plug perforate base of surface casing, circulate cement to surface with 175 sx 65/35 Pozmix 6% gel.

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part  None \_\_\_\_\_

Operations Completed: Hour: 10:30 a.m. Day: 1 Month: 9 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4930' with 4 sx cement on top, DV at 2870',

2nd plug put 100' ft. plug 2920-2820' with bailer,

3rd plug perforated at 900' and pumped 175 sx, lost circulation after 140' sx cement.

9/1/93 4th plug fluid in 5 1/2" at 411', filled to surface.

5th plug pumped 100 sx cement down annulus-pressured up.

Remarks: Used 65/35 Pozmix 6% gel by D & S Cementing. No casing recovery.  
(if additional description is necessary, use BACK of this report)

Observe this plugging.

DATE SEP 15 1993

INV. NO. 38660

Signed Glen R. Barlow  
(TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 09 1993  
CONSERVATION DIVISION  
Wichita, Kansas