

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-00355-00-00
Spot: NENESW Sec/Twnshp/Rge: 6-27S-34W
2310 feet from S Section Line, 2310 feet from W Section Line
Lease/Unit Name: CURRY Well Number: 2
County: HASKELL Total Vertical Depth: 2810 feet

Operator License No.: 5293
Op Name: HELMERICH & PAYNE, INC.
Address: 1579 E. 21ST ST.
TULSA, OK 74017

Conductor Pipe: Size feet: # 91.33
Surface Casing: Size 10.75 feet: 740 WITH 300 SX CMT
Production: Size 5.5 feet: 2686 WITH 750 SX CMT
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 02/26/2001 11:00 AM

Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.

Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: CIBP @ 2507' WITH 2 SX CMT. FILL WITH MUD TO 800'. 25 SX CMT AT 800'. PUMP CMT FORM 300' TO 0'. 10 3/4" X 5 1/2" ANNULUS FULL OF CMT.

Plugging Proposal Received By: RICHARD LACEY
Date/Time Plugging Completed: 02/26/2001 12:45 PM

Witness Type: Plugging Operations 100% Witnessed (Complete)
KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PBTD 2475'. PERFS AT 2522-28, 2568-76, 2602-14, 2622-36, 2622-14'. CIBP SET AT 2475' WITH 2 SX CMT ON TOP. PUMPED DOWN 5 1/2" CASING 41.5 BBL MUD. PUMPED 25 SX CMT @ 800'. PUMP 5 BBL MUD. PUMPED 35 SX CMT FROM 300' - 0'. MAXIMUM PSI 300#. SHUT IN AT 300#. 10 3/4" X 5 1/2" ANNULUS CMT WAS AT SURFACE.

INVOICED

DATE 03-08-2001

INV. NO. 2001061461

RECEIVED
STATE CORPORATION COMMISSION

MAR 6 2001

Remarks: USED COMMON CEMENT BY SARGENTS. NO CASING RECOVERED.

Plugged through: CSG

CONSERVATION DIVISION
Wichita, Kansas

District: 01

Signed

Kevin D. Strube

(TECHNICIAN)

MAR 02 2001

Form CP-2/3