

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-21381-00-01
Spot: N2NENE Sec/Twnshp/Rge: 19-27S-33W
4838 feet from S Section Line, 616 feet from E Section Line
Lease/Unit Name: FREY C Well Number: 5
County: HASKELL Total Vertical Depth: 5480 feet

Operator License No.: 5447
Op Name: OXY USA, INC.
Address: PO BOX 27570 5 E GREENWAY PLZ ST
HOUSTON, TX 77227

Production Casing Size: 5.5 feet: 5480 WITH 345 SX CMT
Surface Casing Size: 8.625 feet: 1748 WITH 550 SX CMT
\$178.10

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/26/2003 10:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 400# HULLS & 25 SX CMT FOR BOTTOM PLUG. PLUG AT 1780' WITH 50 SX CMT. PLUG AT 800' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEVIN STRUBE WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 03/26/2003 5:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:


PBTD 4500'. PERFS AT 2874-98, CIBP @ 4500', 4698-4702, CIBP @ 5000', 5134-5216, CIBP @ 5262', 5282-98'. PUMP 400# HULLS & 25 SX CMT FOR BOTTOM PLUG. LOAD HOLE WITH MUD. 1ST PLUG PULL OUT OF HOLE TO 1775'. LOAD HOLE & PUMP 50 SX CMT. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE TO 800'. LOAD HOLE & PUMP 40 SX CMT. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 10 SX CMT TO SURFACE.

RECEIVED
APR 09 2003
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 2112' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed Jim Holland (TECHNICIAN)

INVOICED
DATE 4-9-03
INV. NO. 2003061401

Form CP 2/3