

To: ✓ 1 020701 8-31
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

15-081-00004.0000
API NUMBER 15- Drill completion date 3/18/56
NE SW NW, SEC. 4, T 27 S, R 34 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5293
Operator: Helmerich & Payne, Inc.
Name & Address: P.O. Box 558
Garden City, KS 67846

3630 feet from S section line
4290 feet from E section line
Pleasant Prairie Unit
Lease Name Well # 54
County Haskell
Well Total Depth 5169 167.99 feet
Conductor Pipe: Size feet
Surface Casing: Size 10 3/4 feet 777

Abandoned Oil Well Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor Helmerich & Payne, Inc. License Number 5293
Address P.O. Box 558, Garden City, KS 67846

Company to plug at: Hour: 8:30 a.m. Day: 30 Month: 8 Year: 19 93

Plugging proposal received from Jim Ford
(company name) Helmerich & Payne, Inc. (phone) 316-276-3693

were: 5 1/2" at 5169' w/550 sx cement, TOC 3395', Perfs at 5095-5106, 5161-67'

1st plug set CIBP at 5050' with 2 sx cement on top,

2nd plug perforate Council Grove at 2954' and squeeze with 100 sx 65/35 Pozmix 6% gel,
wiper plug at 2850',

3rd plug perforate at 2725' and squeeze with 100 sx cement to 2400', 4th plug perforate at
1096' and circulate 175 sx cmt. Plugging Proposal Received by Case Morris
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10 a.m. Day: 31 Month: 8 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5050' with 4 sx cement on top with bailer,

2nd plug perforated at 2960' and pumped 140 sx cement down 5 1/2", displaced to 2300' with
wiper plug-shut in,

3rd plug perforated 5 1/2" at 866' and circulated cement to surface with 225 sx.

Remarks: Used 65/35 Pozmix 6% gel by D & S Cementing. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED
I (and/or ~~XXXXXX~~) observe this plugging.

DATE 9-15-93
INV. NO. 38667

Signed *Glenn R Barlow*
(TECHNICIAN)
RECEIVED
STATE CORPORATION COMMISSION
SEP 09 1993
CONSERVATION DIVISION
WICHITA, KANSAS