

To: 1 020702
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200' COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

8-31

15-081-10092-0000
API NUMBER 15- Drill Completion Date 1/26/62

App. NE NE, SEC. 4, T. 27 S, R. 34 W/E

4620 feet from S section line

720 feet from E section line

Pleasant Prairie Unit
Lease Name _____ Well # 55

TECHNICIAN'S PLUGGING REPORT

Operator License # 5293

Operator: Helmerich & Payne, Inc.

Name & Address P.O. Box 558

Garden City, KS 67846

County Haskell

Well Total Depth 5185 168.51 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 997

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Helmerich & Payne, Inc. License Number 5293

Address P.O. Box 558, Garden City, KS 67846

Company to plug at: Hour: 5:30 p.m. Day: 30 Month: 8 Year: 19 93

Plugging proposal received from James Ford

(company name) Helmerich & Payne, Inc. (phone) 316-276-3693

were: 5 1/2" at 5184' w/125 sx cement, TOC 4400', PBTD 5141', Perfs at 5002-10, 5018-26, 5060-75, 5126-31'

1st plug set CIBP at 4970' with 2 sx cement on top, 2nd plug perforate at Council Grove at 2954'

and squeeze with .100 sx cement, wiper plug at 2850', 3rd plug perforate at 2725' and squeeze

with 100 sx cement to 2400', 4th plug perforate at 1096' and circulate 175 sx cement.

Plugging Proposal Received by _____ Case Morris
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 9:30 p.m. Day: 31 Month: 8 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4950' and put 4 sx cement

2nd plug perforated at 2960' and pumped 140 sx cement, displaced to 2300' with wiper

3rd plug perforated at 1096' and circulated to surface with an excess of 200 sx cement

RECEIVED
STATE CORPORATION COMMISSION
SEP 09 1993
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 65/35 Pozmix 6% gel by D & S Cementing. No casing recovery.

(If additional description is necessary, use BACK of this form.)

I (did) ~~not~~ observe this plugging.

DATE 9-15-93

INV. NO. 38661

Signed Glen P. Barlow
(TECHNICIAN)