

To: 1051885 1-11
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Drill completion 8/12/55

C NW , SEC. 19 , T 27 S, R 31 W/E

3960 feet from S section line

3960 feet from E section line

Lease Name Black Well # 1

County Haskell

Well Total Depth 2715 88.24 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 508

TECHNICIAN'S PLUGGING REPORT

Operator License # 5293

Operator: Helmerich & Payne, Inc.

Name & Address P.O. Box 558

Garden City, KS 67846-0558

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton License Number

Address

Company to plug at: Hour: 9 a.m. Day: 11 Month: 1 Year: 19 95

Plugging proposal received from Allen Dick

(company name) Helmerich & Payne, Inc. (phone) 316-276-3693

Work: 4 1/2" at 2714' w/300 sx cement, PBTB 2703', Perfs at 2664-74, 2684-94'

Tubing and rods sanded into hole. Top of tubing fish 2000'.

1st plug set cement retainer at 1200', pump 35 sx cement through retainer,

2nd plug perforate 4 1/2" casing at 1050' and pump 250 sx cement down 4 1/2", circulating up the 8 5/8" X 4 1/2" annulus to surface.

Plugging Proposal Received by Steve Durrant

(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 1 p.m. Day: 11 Month: 1 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug set cement retainer at 1200' and pumped 35 sx cement through retainer,

2nd plug perforated 4 1/2" at 1050'. Pumped 250 sx cement down 4 1/2", circulating up the 8 5/8"

X 4 1/2" annulus to surface.

RECEIVED STATE CORPORATION COMMISSION

JAN 13 1995 1-13-95

Remarks: Used 65/35 Pozmix 6% gel by Halliburton. No casing recovery.

(if additional description is necessary, use BACK of this form.)

(did observe this plugging.)

Signed Richard M. Lacey (TECHNICIAN)

INVOICED

DATE 1-20-95

INV. NO. 42078