

1-30

To: 1 030998
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 057-20,200-0000

SW SW NW, SEC. 25, T 27 S, R 24 W/EX

2970 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Wenke Well # 1

Operator: TXO Production Corporation
Name & Address: 1660 Lincoln, Suite 1800
Denver, CO 80264

County Ford 169.00

Well Total Depth 5200 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 536

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS

Company to plug at: Hour: 10:25 a.m. Day: 30 Month: 1 Year: 19 89

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 5180' PBSD 5180' Perfs at 5044-52, 4878-82'

1st plug pump 25 sx common cement and 1 sx hulls,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 135 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:10 a.m. Day: 30 Month: 1 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 25 sx common cement to bottom,

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released

8 5/8" wiper plug and pumped 135 sx cement.

RECEIVED STATE CORPORATION COMMISSION

2-1-89 FEB 1 1989

Maximum pressure 500 psi and shut in 350 psi.

CONSERVATION DIVISION

Remarks: Used 60/40 Pozmix 2% gel, 2% cc by B.J. Titan. Recovered 2643' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED
Observe this plugging.

DATE 2-3-89

Signed Steve Dumont (TECHNICIAN)

INV. NO. 23870

1-30