

To: 1 090702  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 057-20,055-0001  
NE NE NW, SEC. 35, T 27 S, R 24 W/X  
4950 feet from S section line  
2970 feet from E section line  
Lease Name Barngrover Well # 3

TECHNICIAN'S PLUGGING REPORT

Operator License # 5817  
Operator: Benson Mineral Group, Inc.  
Name & Address 1560 Broadway, Ste. 1900  
Denver, CO 80202

County Ford 90.02  
Well Total Depth 2770 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 409

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Benson Mineral Group, Inc. License Number 5817  
Address 1560 Broadway, Ste. 1900, Denver, CO 80202

Company to plug at: Hour: 9:30 a.m. Day: 28 Month: 6 Year: 1996

Plugging proposal received from Phil Kempton  
(company name) Benson Mineral Group, Inc. (phone) 303-863-3500

Work: 4 1/2" at 2770' with 100 sx cement, PBD 2746', Perfs at 2682-92'  
1st plug run tubing to 2650' and spot 20 sx cement and 2 sx hulls;  
2nd plug pump 50 sx cement and 10 sx gel at 1650',  
3rd plug pull to 950' and pump 5 sx gel and 80 sx cement, 4th plug pull to 430' and pump 50  
sx cement, 5th plug pull to 40' and pump 10 sx cement.

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 11:30 a.m. Day: 28 Month: 6 Year: 1996

ACTUAL PLUGGING REPORT 1st plug ran tubing to 2650' and spotted 2 sx hulls and 20 sx cement,  
2nd plug pumped 50 sx cement and 10 sx gel at 1650',  
3rd plug pulled to 950' and pumped 5 sx gel and 80 sx cement,  
4th plug pulled to 430' and pumped 50 sx cement,  
5th plug pulled to 40' and pumped 10 sx cement.  
Stayed full of cement.

RECEIVED  
KANSAS CORPORATION COMMISSION  
JUL 02 1996 7-2-96  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: Used common cement by BMG. Recovered 1687' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

I (and/or witnesses) observe this plugging.

INVOICED  
DATE 7-5-96  
INV. NO. 45942  
6-28

Signed \_\_\_\_\_  
(TECHNICIAN)