

To: 1 090701  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 057-20,013-0001

C NE NW, SEC. 35, T 27 S, R 24 W/E  
4620 feet from S section line  
3300 feet from E section line

6-27

TECHNICIAN'S PLUGGING REPORT

Operator License / 5817

Lease Name Barngrover Well # 1

Operator: Benson Mineral Group, Inc.

County Ford

Name & Address 1560 Broadway, Ste. 1900

Well Total Depth 5176 168.22 feet

Denver, CO 80202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 410

Abandoned Oil Well Gas Well X Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Benson Mineral Group, Inc. License Number 5817

Address 1560 Broadway, Ste. 1900, Denver, CO 80202

Company to plug at: Hour: 9 a.m. Day: 27 Month: 6 Year: 1996

Plugging proposal received from Phil Kempton

(company name) Benson Mineral Group, Inc. (phone) 303-863-3541

logs: 5 1/2" at 5165' w/150 sx cement, PBTD 5093', DV @ 2750' w/150 sx cement, Perfs at 5100-10 5076-84'

1st plug run tubing to 5075' and spot 2 sx hulls and 25 sx cement,

2nd plug perforate at 930' and pump in 80 sx cement,

3rd plug shoot casing at 430' and pump in 50 sx cement, 4th plug pull to 30' and top off.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 11:30 a.m. Day: 27 Month: 6 Year: 1996

ACTUAL PLUGGING REPORT 1st plug ran tubing to 5075' and spotted 2 sx hulls and 25 sx cement,

2nd plug perforated casing at 930' and pumped in 80 sx cement,

3rd plug shot casing at 430' and pumped in 50 sx cement,

4th plug pulled to 30' and topped off with 12 sx cement. Stayed full.

RECEIVED  
KANSAS CORPORATION COMMISSION  
JUL 02 1996  
7-2-96  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: Used common cement by BMG. Recovered 430' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

INVOICED  
DATE 7-5-96  
INV. NO. 45943  
6-27

Signed [Signature] (TECHNICIAN)