

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

12-10

API NUMBER: 15-155-01022 0008

rec
7-15-15

C SW SE, SECTION 22 TOWNSHIP 25 RANGE 9 W

OPERATOR LICENSE # 5210
OPERATOR Lebsack Oil Pead Inc.
NAME & P.O. Box 489 1303 Main
ADDRESS Hays, Ks 67601

990 FEET FROM S SECTION LINE
2310 FEET FROM E SECTION LINE

LEASE NAME: Catte # 1 OWWO
COUNTY: Reno
WELL TOTAL DEPTH: 4646 151.00
PIPE: 5 1/2-4270'
SURFACE CASING: 8 5/8-200'

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SWD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

RECEIVED
KANSAS CORPORATION COMMISSION

PLUGGING CONTRACTOR: Mike's Testing & Salvage
ADDRESS: P.O. Box 209 Chase, KS 67524 LICENSE: 31529

JAN 11 1999
1-11-99
CONSERVATION DIVISION
WICHITA, KS

COMPANY TO PLUG AT: HOUR: 9:00 DAY: 10 MONTH: 12 YR: 1998

PLUGGING PROPOSAL RECEIVED FROM: Mike Kelso

COMPANY NAME: Mike's Tesing & Salvage PHONE: 316-938-2943
WERE: Sand to 3750', five sacks of cement. Thirty-five sacks of
cement at 800'. Thirty-five sacks of cement at 1350'. Two hundred
and fifty sacks of cement at 0'

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 27 1999

PLUGGING PROPOSAL RECEIVED BY: J.L.

CONSERVATION DIVISION
WICHITA, KS

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART (_____) NONE (_____)

COMPLETED: HOUR: _____ DAY: 10 MONTH: 12 YEAR: 1998

ACTUAL PLUGGING REPORT: Sanded bottom to 3750' and five sacks of common
shot. 5 1/2" casing off at 2600'. Pulled to 1350' and pumped
thirty-five sacks of cement Pulled to 300'. Pumped thirty-five
sacks of cement. Pulled to 250'. Circulated cement to surface.

REMARKS: 60/40 pos mix with 4% gel by Allied. Invoice # 7736

I DID OBSERVE THIS PLUGGING.

Jack Luthi
JACK LUTHI

1-28-99
60593