

2-070745

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 207B
Wichita, Kansas 67202

10-27

API NUMBER: 15-155-21,112-0000

C NE SW, SECTION 33 TOWNSHIP 25 RANGE 8W

OPERATOR LICENSE # 3536 1980 FEET FROM S SECTION LINE

OPERATOR RAMCO ENERGY CORPORATION 3630 FEET FROM E SECTION LINE

NAME & P.O. BOX 340

ADDRESS GREAT BEND, KS 67530

LEASE NAME: MELVIN MINOR #2

COUNTY: RENO 129.97

WELL TOTAL DEPTH: 3999'

PIPE: 5 1/2" @ 3998'

SURFACE CASING: 8 5/8" @ 344'

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED:

PLUGGING CONTRACTOR: MIKE'S TESTING & SALVAGE INC

ADDRESS: LICENSE: 31529

COMPANY TO PLUG AT: HOUR: 9:00 DAY: 27 MONTH: 10 YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: MONTE JOE

COMPANY NAME: MIKE'S TESTING & SALVAGE INC PHONE: (316) 938-2943

WERE: SAND TO 3752' AND 5 SACKS

35 SACKS AT 1400'

35 SACKS AT 700'

400' TO SURFACE

RECEIVED
KANSAS CORPORATION COMMISSION
11-19-97
NOV 19 1997

PLUGGING PROPOSAL RECEIVED BY: JACK LUTHI

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (X) PART NONE

COMPLETED: HOUR: 1:30 DAY: 27 MONTH: 10 YEAR: 1997

ACTUAL PLUGGING REPORT: SANDED BOTTOM TO 3752' AND 5 SACKS. SHOT 5 1/2" CASING OFF AT 3000'. PULLED TO 1400', PUMPED 35 SACKS. PULLED TO 700', PUMPED 35 SACKS. PULLED TO 400', PUMPED CEMENT TO SURFACE.

CONSERVATION DIVISION
WICHITA, KS

REMARKS: 60/40 POZ 4% GEL ALLIED #9654

INVOICED

DATE NOV 20 1997

INV. NO. 49547

I DID OBSERVE THIS PLUGGING.

Jack Luthi
JACK LUTHI