

2-070746

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

10-29

API NUMBER: 15-155-21,113 - 0000

C NW SW, SECTION 33 TOWNSHIP 25 RANGE 8W

OPERATOR LICENSE # 3536 1980 FEET FROM S SECTION LINE

OPERATOR RAMCO ENERGY CORPORATION 4620 FEET FROM E SECTION LINE

NAME & P.O. BOX 340

ADDRESS GREAT BEND, KS 67530

LEASE NAME: MELVIN MINOR #3

COUNTY: RENO

WELL TOTAL DEPTH: 4320' 140.40

PIPE: 5 1/2" @ 4319'

SURFACE CASING: 8 5/8" @ 333'

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED:

PLUGGING CONTRACTOR: MIKE'S TESTING & SALVAGE INC

ADDRESS: P.O. BOX 467, CHASE, KS 67524 LICENSE: 31529

COMPANY TO PLUG AT: HOUR: 11:30 DAY: 29 MONTH: 10 YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: MONTE JOE

COMPANY NAME: MIKE'S TESTING & SALVAGE INC PHONE: (316) 938-2943

WERE: SAND TO 3780', 5 SACKS

35 SACKS AT 1400'

35 SACKS AT 700'

380' TO SURFACE

RECEIVED
KANSAS CORPORATION COMMISSION
11-19-97
NOV 19 1997

PLUGGING PROPOSAL RECEIVED BY: J.L.

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (X) PART () NONE ()

COMPLETED: HOUR: 4:30PM DAY: 29 MONTH: 10 YEAR: 1997

ACTUAL PLUGGING REPORT: SANDED BOTTOM TO 3780', 5 SACKS OF COMMON. SHOT 5 1/2" CASING OFF AT 3000'. PULLED TO 1400', PUMPED 35 SACKS. PULLED TO 700, PUMPED 35 SACKS. PULLED TO 380', CIRCULATED CEMENT TO SURFACE.

CONSERVATION DIVISION
WICHITA, KS

REMARKS: 60/40 POZ 4% GEL ALLIED #4435

INVOICED

DATE NOV 20 1997

INV. NO. 49548

I DID OBSERVE THIS PLUGGING.

Jack Luthi
JACK LUTHI