

AFFIDAVIT OF COMPLETION FORM

ACO-1

This form shall be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ten days after the completion of the well, regardless of how the well was completed. Circle one: Oil, gas, dry, SWD, OWWO, injection. Type and complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316)263-3238.

OPERATOR Bowers Drilling Company, Inc.

API NO. 15-151-20,977-0000

ADDRESS 125 North Market, Suite 1425
Wichita, Kansas 67202

COUNTY Pratt

FIELD Barnes

**CONTACT PERSON Emil E. Bowers

PROD. FORMATION Viola

PHONE 262-6449

LEASE Fincham

PURCHASER Central States Gas Co.


WELL NO. 3

ADDRESS Box 407
Pratt, Kansas

WELL LOCATION NW NE SE SW ANB ECC
2310 Ft. from South Line and
990 Ft. from East Line of
the SW SEC. 25 TWP 27S RGE. 12W

DRILLING CONTRACTOR Gabbert - Jones, Inc.
ADDRESS Sutton Place
Wichita, Kansas

PLUGGING CONTRACTOR ADDRESS



WELL PLAT

KCC
KGS
MISC
(Office Use)

TOTAL DEPTH 4306 PBTD

SPUD DATE 7/15/81 DATE COMPLETED waiting on connection

ELEV: GR 1751 DF 1754 KB 1756

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS (New) / (Used) casing.
CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Conductor	16"	13 3/8	40#	84'	Common	100	
Surface	12 1/4"	8 5/8	24#	837'	Common	575	3%cc-2% gel
Production	7 7/8	4 1/2	10.5	4305	50-50 Pos.	250	18% salt

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			4	1/2" Jet	4246-50

TUBING RECORD

Size	Setting depth	Packer set at
2 3/8	4260	---

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
1,000 Gal. M.C.A.	4246-50

RECEIVED
STATE CORPORATION COMMISSION

DEC - 4 1981

Date of first production W. O. Conn. Producing method (flowing, pumping, gas lift, etc.) Flow Gravity

RATE OF PRODUCTION PER 24 HOURS Oil 0 Gas W.O.Conn. Water 0 %

Disposition of gas (vented, used on lease or sold) To be sold Perforations 4246-50

**The person who can be reached by phone regarding any questions concerning this information. A witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

WICHITA, KANSAS
STATE CORPORATION COMMISSION
RECEIVED
DEC 4 1981

Name of lowest fresh water producing stratum unknown Depth 200'

Estimated height of cement behind Surface Pipe to surface.

DV USED? no

WELL LOG

Formation Description, Contents, etc.	Top	Bottom	Name	Depth
Sand - Shale	3410		Douglas	3410
Lime	3592	3954	Lansing	3592
Chert	4034	4090	Mississippi	4034
Lime	4090		Miss.Lime	4090
Sand	4166		Kinderhook	4166
Lime	4240		Viola	4240

AFFIDAVIT

STATE OF KANSAS, COUNTY OF SEDGWICK SS, _____

Emil E. Bowers OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH,
DEPOSES THAT HE IS President (~~FOR~~) (OF) Bowers Drilling Co., Inc.
OPERATOR OF THE Fincham LEASE, AND IS DULY AUTHORIZED TO MAKE

THIS AFFIDAVIT FOR AND ON THE BEHALF OF SAID OPERATOR, THAT WELL NO. 3 ON
SAID LEASE/ ~~THIS WELL HAS BEEN COMPLETED AS OF THE~~ IS WAITING ON CONNECTION ~~XXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXX~~, AND THAT
ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH NOT.

SUBSCRIBED AND SWORN BEFORE ME THIS 1st DAY OF December 1981
(S) Emil E. Bowers
Emil E. Bowers

MY COMMISSION EXPIRES: March 2, 1984
Judy C. Ridder
NOTARY PUBLIC
Judy C. Ridder

JUDY C. RIDDER
STATE NOTARY PUBLIC
SEDGWICK COUNTY, KANSAS
MY APPT. EXP. 3/2/84