

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Kiowa County, Sec. 8 Twp. 27 Rge. 18 (EX) (W)

Location as "NE/CNW/SW" or footage from lines C NE SE

Lease Owner Aylward Drilling Company et al

Lease Name Grizzell Well No. 1

Office Address 813 1st Natl. Bank Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed February 11 19 59

Application for plugging filed February 11 19 59

Application for plugging approved February 11 19 59


Plugging commenced February 11 19 59

Plugging completed February 11 19 59

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot - St. John, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4969 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	395	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Fill hole with heavy mud from total depth to 400'; set Halliburton plug at 400' with 1/2 sack of hulls and 20 sacks of cement on top of plug; heavy mud to 35'; set Halliburton plug at 35' with 1/2 sack of hulls and 10 sacks of cement to top of surface.

RECEIVED  
STATE CORPORATION COMMISSION  
APR 21 1959  
CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Aylward Drilling Company

Address 813 1st Natl. Bank Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Paul W. Hesse (employee of owner) or (owner/producer) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul W. Hesse

813 1st Natl. Bank Bldg. - Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 16th day of February, 19 59

My commission expires December 11, 1961

Duane Jessup Notary Public.

PLUGGING  
FILE SEC. 8 T. 27 R. 18W  
BOOK PAGE 15 LINE 6

GRIZZELL NO. 1

Casing Record:  
8 5/8" - 395'

Company: Aylward Drilling Company et al  
Contractor: Aylward Drilling Company

Location: C NE SE 8-27-18W  
Kiowa County  
Kansas

Commenced: January 23, 1959  
Completed: February 11, 1959

Elevation: K.B. 2194'

	<u>From</u>	<u>To</u>	<u>Remarks</u>
Sand & Gravel	0	250	Set 8 5/8" surface pipe at 395' 3/300 sacks cement
Shale & Red Rock	250	475	
White sand-fine	475	500	
Red Shale & Shells	500	1125	Geological Tops:
Shale & Streaks lime	1125	1175	
Anhydrite Lime	1175	1235	Heebner
Shale & Lime	1235	1335	Toronto
Shale & Shells	1335	2075	Base/Oread
Lime & Shale	2070	2380	Brown Lime
Shale & Lime	2380	2475	Lansing
Shale & Lime Stringers	2475	2480	B/Kansas City
Lime	2480	2630	Conglomerate
Lime & Shale	2630	2660	Miss.
Lime w/Shale	2660	2740	Kinderhook
Lime & Shale	2740	2800	Kinderhook Sand
Shale & Lime	2800	2890	Viola
Lime & Shale	2890	3065	
Shale & Lime	3065	3220	
Lime & Shale	3220	3315	
Shale	3315	3470	DST 4779-89 Open 75". Fair to wk.
Shale w/Lime	3470	3525	blow. Rec. 65' Wtry mud w/show tar
Lime & Shale	3525	3575	oil. IBHP 1510#/20", FBHP 220#/30"
Shale & Lime	3575	3630	FP 0#-0#.
Shale & Sandy Lime	3630	3725	
Lime, Chalk & Shale	3725	3815	
Lime & Shale	3818	4035	
Lime	4035	4110	
Sandy Lime & Shale	4110	4195	
Lime	4195	4570	
Lime & Shale	4570	4625	
Lime	4625	4765	
Lime w/sml. Chert String	4765	4775	
Lime	4775	4799	
Lime & Chert	4799	4838	
Lime	4838	4918	
White Sand	4918	4933	
Lime	4933	4965	
Lime & Chert	4965	4969	T.D.

D & A

**RECEIVED**  
STATE CORPORATION COMMISSION  
APR 21 1959  
CONSERVATION DIVISION

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

*Paul W. Hesse*

Subscribed and sworn to before me this 16th day of February, 1959.

*Duane Jessup*  
DUANE JESSUP Notary Public

My commission expires December 11, 1961

**PLUGGING**  
FILE SEC. 8 T. 27 R. 18w  
BOOK PAGE 15 LINE 6