

STATE OF KANSAS
STATE CORPORATION COMMISSION
D. S. Market, Room 2078
Topeka, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-097-20,293-0000

LEASE NAME Miller

WELL NUMBER 3

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 25 TWP. 27S RGE. 18W (E) or (W)

COUNTY Kiowa

Date Well Completed

Plugging Commenced 12-3-98

Plugging Completed 12-4-98

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR T.T. Production, Inc.

ADDRESS R.R. #1, Box 91, Haviiland, Ks. 67059

PHONE#(316) 723-2944 OPERATORS LICENSE NO. 31919

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

Richard Lacey (KCC District Agent's Name)

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.O. 4305'

How depth and thickness of all water, oil and gas formations.

12-15-98

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	290'	None
				3 1/2"	4292'	2020'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plug used, state the character of same and depth placed, from feet to feet each side. Pumped bottom plug with 15 sks. cement and 50# hulls and displaced to 3645'. Shot pipe loose pulled to to 1090', pumped 50 sks. cement, pulled to 320', pumped 50 sks. cement, pulled to 40' and circulated 20 sks. cement to surface, 60/40 pos 6% gel. Plugging Complete

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467, Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: T.T. Production, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

I, above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467, Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 14th day of December, 1998

[Signature]
Notary Public

My Commission Expires:

