

KANSAS

IMPORTANT
Kans. Geo. Survey request
samples on this well.

WELL COMPLETION REPORT AND
DRILLER'S LOG


S. 2 T. 27S R. 17 ^{EX} W

API No. 15 — 097 — 20,715
County Number

Loc. C SW NW

County Kiowa

640 Acres
N



Elev.: Gr. 2113

DF 2115 KB 2118

Operator
Hummon Corporation

Address
400 One Main Place, Wichita, KS. 67202

Well No. #1 Lease Name **Cecil**

Footage Location
660 feet from O&G (S) line **660** feet from X&E (W) line

Principal Contractor **D. R. Layck Oil Company** Geologist **Tim Pierce**

Spud Date **2/24/81** Date Completed **4/5/81** Total Depth **4720** P.B.T.D.

Directional Deviation Oil and/or Gas Purchaser
Kansas Nebraska Gas

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12½	8-5/8"	24#	359	Common	250 sx	2% gel 3% cc
Production		4½"	10.5	4665.87	60-40 Poz	125 sx	10% salt, 6/10ths 1% Halad 9, 3/4 c 1% CFR2.

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type SSB	Depth interval
			4		4600-03'

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Acidized w/ 250 gal. 7½% MCA w/ 1 gal. PEN5	4600-03
Foam frac w/ 17,500 gal. foam, 7500# 20-40 Sand	4600-03

INITIAL PRODUCTION

Date of first production Producing method (flowing, pumping, gas lift, etc.)

RATE OF PRODUCTION PER 24 HOURS Oil bbls. Gas-oil ratio CFPB

Disposition of gas (vented, used on lease or sold) Producing interval (s) **4600-03'**

CONSERVATION DIVISION
WICHITA, KANSAS

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on an open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

RECEIVED
STATE CORPORATION COMMISSION
AUG 31 1982

Operator
Hummon Corporation

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:
gas

Well No. #1

Lease Name Cecil

S 2 T 27^{EX} R 17 W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1: 4568-4604'			ELECT. LOG TOPS	
OP 30-45-30-45				
GTS in 4 min.				
1st opening after 15 min. gauged 326 MCF	FP 106-96		Heebner	3923 -1805
20 " " 326 "	SIP 1536-1507		Lans	4092 -1974
25 " " 326 "	BHT 118°		B/KC	4398 -2280
30 " " 340 "			Cher SH	4573 -2455
			Cher Sd	4600 -2482
			Miss	4641 -2523
2nd opening initial 2 min. gauged 188 MCF			Kind SH	4694 -2576
10 min. " 340 "			Kind Sd	4711 -2593
20 " " 340 "			RTD 4720	
30 " " 340 "			LTD 4724	

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Wilber Berg
Signature
Wilber Berg
Title
Date

Hummon Corporation
400 One Main Place
Wichita, Kansas 67202

Cecil #1
C SW NW Sec. 2-27S-17W
Kiowa County, Kansas

Contractor: D. R. Lauck Oil Company, Inc.
221 S. Broadway, Suite 400
Wichita, Kansas 67202

Commenced: February 24, 1981
Completed: March 5, 1981

Drillers Log

Sand	220
Blue Shale	406
Red Bed	1063
Anhydrite	1077
Red Bed & Shale	1400
Shale	1856
Shale & Shells	3340
Shale & Lime	3765
Shale & Shells	4010
Lime & Shale	4175
Shale & Lime	4310
Lime & Shale	4434
Lime	4720 RTD