


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Kiowa County. Sec. 4 Twp. 27S Rge. 17W E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
C-NE/4

Lease Owner Bold Oil Co. and Paul Condit, Individual
Lease Name Rich Bradley Well No. 1
Office Address P. O. Box 48, Fellsburg, KS 67048
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole



Locate well correctly on above Section Plot

Date Well completed November 19, 1980
Application for plugging filed Verbal Application 19
Application for plugging approved Verbal Approval 19
Plugging commenced November 19, 1980
Plugging completed November 19, 1980
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well William T. Owen
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5,050'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	405'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 5,050 ft. (rotary total depth) to 440 ft. Set plug at 440 ft. and cemented with 60 sacks cement. Filled hole with heavy rotary mud from 440 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 10 sacks cement, 10 sacks cement in rat hole.

Plugging operations accomplished utilizing Sun Oil Well cementing pump truck through 4 1/2 inch drill pipe.

(If additional description is necessary, use BACK of this form)
Name of Plugging Contractor Sun Oil Well Cementing, Inc.
Box 169, Great Bend, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.
Gary Younger, Agent of owner

I, the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gary Younger
251 N. Water - Suite 10, Wichita, KS 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of November, 1980

Elsie Willison
Elsie Willison - Notary Public.

commission expires July 25, 1982

RECEIVED
DEC 16 1980
12-16-80
CONSERVATION DIVISION
Wichita, Kansas

