

State of Kansas



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JUL 14 1969
CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Patterson of Graham-Michaelis has this

date requested permission to plug the following described well:

Mr. Patterson guarantees payment of the plugging fee.

Operator's full Name: Graham-Michaelis Drilling Co.

Complete Address: 211 N. Broadway, Wichita, Kansas

Lease Name: Plummer Well No. 1

Location: App C SE Sec. 4 Twp. 27 Rge. 40 (E)(W)

County: Stanton Total Depth 2286' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Patterson was instructed to plug the well as follows:

8 5/8" to 560' circulated w/ cement. 5 1/2" to 2279' cemented.

Open Hole 2279' to T.D. Plug bottom w/ 10 sacks cement.

Top of cement. 2160' Mud 2160' to 560'.

Spot 45 sacks cement 560' to 430' Mud 430' to 45'

Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,

Edgar J. Eves
Conservation Division Agent