

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION
APR 15 1970
CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Makemson of Cities Service Oil has this

date requested permission to plug the following described well:

Mr. Makemson guarantees payment of the plugging fee.Operator's full Name: Cities Service Oil Co.Complete Address: Box 1098, Liberal, KansasLease Name: George S. Frey Well No. 1-CLocation: SE NW Sec. 19 Twp. 27 Rge. 33 ~~(E)~~ (W)County: Haskell Total Depth 2773' Oil WellGas Well X Input Well SWD Well D & A X Lost HoleMr. Makemson was instructed to plug the well as follows:

10 3/4" to 600' circulated w/ cement. 7" to 262 1/2' cemented.

5 1/2" liner 2590' to T.D. No Perforations

Plug bottom w/ 150 sacks cement Top of cement 2350'

Mud 2350' to 600' Spot 30 sacks cement 600' to 480'

Mud 480' to 40' Plug, Hulls & 10 sacks cement 40' to 0'.

Very truly yours,

Conservation Division Agent